

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	33
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STORM SEWER SCHEDULE (CONTINUED)

STR #	UPSTREAM STRUCTURE			DOWNSTREAM STRUCTURE			PRECAST REINFORCED CONCRETE FLARED END SECTIONS		REINFORCED CONCRETE PIPE TEE						JUNCTION BOX NO.1	PRECAST CONCRETE BOX CULVERT, 1.5M x 0.6M	BOX CULVERT END SECTION, CULVERT NO. 7
	LOCATION		LT/RT	LOCATION		LT/RT	600MM	1050MM	300MM PIPE WITH 300MM RISER	450MM PIPE WITH 300MM RISER	600MM PIPE WITH 300MM RISER	750MM PIPE WITH 300MM RISER	900MM PIPE WITH 300MM RISER	1050MM PIPE WITH 300MM RISER			
	STATION	OFFSET METER		STATION	OFFSET METER		M542E128 EACH	M542E148 EACH	M542C212 EACH	M542C220 EACH	M542C228 EACH	M542C236 EACH	M542C244 EACH	M542C248 EACH			
137	3+291.348	6.200	RT	138	3+291.348	6.200	LT										
139	3+263.000	4.475	RT	140	3+263.000	4.475	LT										
140	3+263.000	-4.475	LT	0	3+263.000	6.200	LT						1				
186	3+216.576	14.300	RT	141	3+218.395	6.000	RT										
141	3+218.395	6.000	RT	142	3+230.000	4.475	RT										
142	3+230.000	4.475	RT	143	3+230.000	4.475	LT										
143	3+230.000	-4.475	LT	144	3+230.000	6.200	LT										
145	3+215.745	-10.600	LT	0	3+215.745	6.200	LT						1				
0	3+206.645	14.300	RT	147	3+204.448	6.200	RT										
148	3+192.000	4.475	RT	0	3+192.000	6.200	RT						1				
149	3+173.000	4.475	RT	150	3+173.000	6.200	RT										
151	3+152.000	-4.475	LT	152	3+152.000	4.475	RT										
152	3+152.000	4.475	RT	0	3+152.000	6.200	RT						1				
155	3+129.452	-6.200	LT	156	3+115.748	6.200	LT										
156	3+115.748	-6.200	LT	158	3+115.748	6.200	RT										
157	3+118.225	12.200	RT	158	3+115.748	6.200	RT										
159	3+090.000	4.475	RT	0	3+090.000	6.200	RT						1				
160	3+062.000	-4.475	LT	161	3+062.000	4.475	RT										
161	3+062.000	4.475	RT	162	3+062.000	6.200	RT										
163	3+036.000	4.475	RT	0	3+036.000	6.200	RT						1				
164	3+010.000	-4.475	LT	165	3+010.000	4.475	RT										
165	3+010.000	4.475	RT	0	3+010.000	6.200	RT						1				
166	2+984.395	-6.000	LT	167	2+970.205	6.000	LT										
167	2+970.205	-6.000	LT	168	2+970.205	4.475	RT										
168	2+970.205	4.475	RT	169	2+970.205	6.200	RT										
170	2+927.500	-4.475	LT	171	2+927.500	4.475	RT										
171	2+927.500	4.475	RT	0	2+927.500	6.200	RT							1			
172	2+905.000	-6.200	LT	174	2+885.248	6.200	LT										
174	2+885.248	-6.200	LT	175	2+885.248	4.475	RT										
175	2+885.248	4.475	RT	0	2+885.248	6.200	RT							1			
176	2+863.000	-6.500	LT	177	2+863.000	4.475	LT										
177	2+863.000	-4.475	LT	179	2+863.000	6.200	RT										
178	2+863.000	8.300	RT	179	2+863.000	6.200	RT										
180	2+833.000	4.475	RT	0	2+833.000	6.200	RT							1			
181	2+803.000	4.475	RT	183	2+803.000	6.200	RT										
182	2+803.000	8.300	RT	183	2+803.000	6.200	RT										
173	2+896.595	-10.300	LT	0	2+896.595	6.200	LT			1							
300	3+576.965	11.800	RT	301	3+576.974	10.300	RT										
301	3+576.974	10.300	RT	302	3+582.000	6.375	RT										
302	3+582.000	6.375	RT	304	3+582.000	4.500	LT										
304	3+582.000	4.500	LT	307	3+617.600	4.500	LT										
307	3+617.600	4.500	LT	313	3+657.000	4.500	LT										
313	3+657.000	4.500	LT	319	3+690.350	4.500	LT										
319	3+690.350	4.500	LT	322	3+723.000	4.500	LT										
322	3+723.000	4.500	LT	326	3+739.000	4.500	LT										
326	3+739.000	4.500	LT	327	3+752.652	6.200	LT										
327	3+752.652	6.200	LT	333	3+800.000	6.200	LT										
333	3+800.000	6.200	LT	338	3+845.000	6.200	LT										
338	3+845.000	6.200	LT	341	3+876.000	6.200	LT										
341	3+876.000	6.200	LT	342	3+899.656	6.200	LT										
342	3+901.180	6.200	LT	401	3+960.405	6.200	LT							1			
401	3+960.405	6.200	LT	402	3+961.400	7.195	LT							64.400		1	
402	3+961.400	7.195	LT	403	3+961.400	11.000	LT										
303	3+582.000	6.375	LT	304	3+582.000	4.500	LT										
305	3+617.600	6.375	RT	307	3+617.600	4.500	LT										
306	3+617.600	6.375	LT	307	3+617.600	4.500	LT										
308	3+654.825	12.000	RT	309	3+656.750	12.000	RT										
309	3+656.750	12.000	RT	312	3+657.000	6.850	RT										
312	3+657.000	6.850	RT	313	3+657.000	4.500	LT										
314	3+654.825	11.900	LT	315	3+657.130	11.900	LT										

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">STORM SEWER SCHEDULE</p> <p>SCALE _____ DRAWN BY KOJ</p> <p>DATE FEBRUARY 6, 2009 CHECKED BY LWJ</p>

PLOT DATE = 2/05/2009
FILE NAME = H:\4420\Contract\74349\SHIT_021_sch_stormsewer_VB.dgn