STORM SEWER SCHEDULE (CONTINUED)

UPSTREAM STRUCTURE				DOWNSTREAM STRUCTURE				TRENCH BACKFILL	STORM SEWERS, CLASS B	STORM SEWERS, CLASS A						RESTRICTED DEPTH MANHOLES							INLETS, TYPE A			INLETS, TYPE B	
									TYPE 1	TYPE 1						TYPE 1 FRAME, CLOSED LID				TYPE 3 FRAME AND GRATE			TYPE 3 FRAME AND GRATE	TYPE 8 FRAME AND GRATE	TYPE 11 FRAME AND GRATE	TYPE 3 FRAME AND GRATE	TYPE 8 GRATE
STR #	LOCATION			STR #	LOCATION				150MM	300MM	450MM	600MM	750MM	900MM	1050MM	1.2 M	1.5 M	1.8 M	2.4 M	1.2 M	1.5 M	1.8 M					
	STATION	OFFSET	LT/RT		STATION	OFFSET	LT/RT	M2080150	M5500215	M5500430	M5500450	M5500465	M5500475	M5500485	M5500495	M6022110	M6022210	M6022310	M6023255	M6022115	M6022215	M6022315	60235700	60236200	60236800	60240220	60240301
		METER				METER		CU M	METER	METER	METER	METER	METER	METER	METER	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
EX	4+379.915	9.016	LT	526	4+403.640	7.860	LT	9.287		22.934																	
526	4+403.640	7.860	LT	527	4+403.640	4.475	RT	5.610		11.516																	1
527	4+403.640	4.475	RT	528	4+403.640	6.200	RT	0.167		0.581																1	
529	4+451.600	4.475	RT	530	4+451.600	11.000	RT	2.258		5.563													1				
TOTALS								2945.228	7.200	705.053	242.233	760.803	180.086	319.795	193.778	9.000	17.000	10.000	1.000	2.000	1.000	5.000	84.000	10.000	2.000	34.000	2.000
TOTALS ROUNDED FOR SUMMARY SHEET								2946	7.2	705.1	242.3	760.9	180.1	319.8	193.8	9	17	10	1	2	1	5	84	10	2	34	2

FOR MORE ITEMS, SEE NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

SCALE | DRAWN BY KOJ

DATE FEBRUARY 6, 2009 | CHECKED BY LWJ

H. M. & G. NO. 4420

PLOT DATE = 2/6/2009
FILE NAME = H:\4420\Contract 74349\SHT_031_sch_stormsewer_V8.dgn