

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	RAISED REFLECTIVE PAVEMENT MARKER
	FEET	FT	SQ FT	FT		FT	FT	FT	FT	FT	SQ FT	SQ FT	EACH
TOLEDO COURTHOUSE SQUARE	-	-	-	-	3228.0	3228.0	-	-	-	-	42.8	42.8	-
8+00.00 TO 20+56.00	1256.0	502.4	41.9	2826.0	-	2826.0	-	-	-	-	-	-	16
20+56.00 TO 90+48.17	6992.2	2796.9	233.1	21814.1	-	21814.1	-	-	-	-	-	-	87
90+48.17 TO 91+73.83	125.7	50.3	4.2	408.4	-	408.4	-	-	-	-	-	-	2
91+73.83 TO 160+84.70	6910.9	2764.3	230.4	18006.1	-	18006.1	-	-	-	-	-	-	86
160+87.58 TO 172+68.00	1180.4	472.2	39.3	2655.9	-	2655.9	-	-	-	-	-	-	21
172+68.00 TO 186+18.00	1350.0	642.4	53.5	-	6615.0	6615.0	256.0	256.0	255.0	255.0	46.8	46.8	65
186+18.00 TO 228+87.80	4269.8	1707.9	142.3	11908.9	-	11908.9	-	-	-	-	-	-	59
228+87.80 TO 245+11.75	1624.0	649.6	54.1	5564.4	-	5564.4	-	-	-	-	-	-	20
245+11.75 TO 248+10.25	298.5	119.4	10.0	1008.6	-	1008.6	-	-	-	-	-	-	4
248+10.25 TO 251+32.00	321.8	128.7	10.7	1171.7	-	1171.7	-	-	-	-	-	-	4
251+32.00 TO 260+80.00	948.0	379.2	31.6	3792.0	-	3792.0	-	-	-	-	-	-	12
260+80.00 TO 265+76.70	496.7	198.7	16.6	1986.8	-	1986.8	-	-	-	-	-	-	6
TOTALS	25774	10412	868	71143	9843	80986	256	256	255	255	90	90	382

FILE NAME = c:\pwork\PW\DOT\STEFFENMK\0123229\0	USER NAME = steffenmk 74379-sh1-sched.dgn	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES				F.A.P. RTE. 773	SECTION •	COUNTY Cumberland	TOTAL SHEETS 26	SHEET NO. 14
PLOT SCALE = 58.0000' / IN.	CHECKED -	REVISED -	SCALE:		SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 74379			
PLOT DATE = 2/6/2009	DATE -	REVISED -	ILLINOIS FED. AID PROJECT										
*110RS-1,(111,111)RS-2,F-ZRS-1													