

BRIDGE DECK SEALING

STRUCTURE NUMBER	DECK WIDTH (FEET)	DECK LENGTH (FEET)	APPROACH SHOULDER PAVEMENT LENGTH (FEET)		APPROACH SHOULDER PAVEMENT WIDTH (FEET)		CONCRETE SEALER			BRIDGE DECK CONCRETE CRACK SEALER FOOT	SILICONE JOINT SEALER FOOT
							DECK AREA SQ FT	APPROACH SHOULDER AREA SQ FT	PARAPET TOP & FACE AREA SQ FT		
							DRIVING (FEET)	PASSING (FEET)	SO FT		
028-0011	40.0	127.5	15.0	15.0	10.0	6.0	5100	480	1074	323	98
								6654			
028-0014	40.0	163.0	15.0	15.0	10.0	6.0	6520	480	1316	403	86
								8316			
TOTALS								14,970		726	184

PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	PERFORMED PAVEMENT MARKING				SHORT TERM	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH	RAISED REFLECTIVE PAVEMENT MARKERS EACH	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT
	LINE 6"	LINE 4"		LINE 8"	PAVEMENT MARKING			
	SKIP DASH WHITE FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT	EDGE LINE DIAGONALS FOOT			
SOUTHBOUND								
7+20.0 TO 101+81.3	2365	9461	9461		757	119	119	252
101+81.3 TO 103+60.0	GAP FOR SN 028-0014 GUN CREEK BRIDGE							
103+60.0 TO 113+00.0	SB REST AREA RAMPS SEE BELOW							
113+00.0 TO 130+00.0	425	1700	1700		136	22	22	45
130+00.0 TO 142+00.0	SB REST AREA RAMPS SEE BELOW							
142+00.0 TO 157+00.0	375	1500	1500		120	19	19	40
157+00.0 TO 164+00.0	IL 154 INTERCHANGE SEE BELOW							
164+00.0 TO 186+00.0	550	2200	2200		176	28	28	59
186+00.0 TO 197+00.0	IL 154 INTERCHANGE SEE BELOW							
197+00.0 TO 303+82.0	2671	10682	10682		855	134	134	285
303+82.0 TO 305+06.0	GAP FOR SN 028-0011 MARCUM BRANCH BRIDGE							
305+06.0 TO 469+00.0	4099	16394	16394		1312	205	205	437
SOUTHBOUND REST AREA								
103+60.0 TO 113+00.0	235	1012	1016	874	81	78	78	27
130+00.0 TO 142+00.0	361	1485	1296	202	100	15	15	33
IL 154 INTERCHANGE								
157+00.0 TO 164+00.0	175	723	725	672	58	45	45	19
186+00.0 TO 197+00.0	275	1512	1155	362	93	14	14	31
TOTALS	11,530	46,669	46,129	2,110	3,687	677	677	1,229
		92,799						

FILE NAME =	USER NAME = colemm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BRIDGE DECK SEALING AND PAVEMENT MARKING SCHEDULES			F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pw_work\pwwork\colemm\d0115620\d978112	2_sht.misc.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	57	FRANKLIN	47 16
	PLOT SCALE = 1/8" = 100' / IN.	CHECKED -	REVISED -		CONTRACT NO. 78112								
	PLOT DATE = 2/4/2009	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								