

SCHEDULE OF QUANTITIES

SHEET 3 OF 9

40600982 HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT

STATION	TO	STATION	LENGTH (FT)	AVERAGE WIDTH (FT)	AREA (SQ YD)
IL 119 MAINLINE					
626+00.00		626+30.00	30.00	26.00	86.67
729+59.30		729+89.33	30.00	26.00	86.67
732+02.55		732+32.55	30.00	26.00	86.67
868+61.40		869+11.40	50.00	26.00	144.44
869+20.30		869+70.30	50.00	26.00	144.44
1030+47.00		1030+77.00	30.00	29.00	96.67
BISMARCK RD					
121+34.00		121+64.00	30.00	26.00	86.67
TOTAL =					732.23 SQ YD
USE =					732.00 SQ YD

* NOTE: SEE INCIDENTAL HOT-MIX ASPHALT SURFACING SCHEDULE FOR PRIVATE ENTRANCE QUANTITIES

44000157 HOT-MIX ASPHALT SURFACE REMOVAL, 2"

STATION	TO	STATION	LENGTH (FT)	AVERAGE WIDTH (FT)	AREA (SQ YD)
IL 119 MAINLINE					
759+60.00		767+60.00	800.00	20.00	1777.78
767+60.00		769+65.00	205.00	30.00	683.33
ALVIN SPUR					
765A+20.00		769A+65.00	445.00	22.00	1087.78
ALVIN SPUR CONNECTOR					
LT		767+76.00		VARIES	398.27
TOTAL =					3,947.16 SQ YD
USE =					3,947.00 SQ YD

SIDEROAD CULVERTS

LOCATION	50105210 REMOVE EXISTING CULVERTS (FOOT)	2800300 TEMPORARY DITCH CHECKS (EACH)	28000500 INLET AND PIPE PROTECTION (EACH)	54207165 P CUL 1 RC-E EQRS 30 (FOOT)	542A0220 P CUL CL A 1 15 (FOOT)	54213660 PRC FLAR END SEC 15 (EACH)	54214515 PRC FL END S EQRS 30 (EACH)	20900110 POROUS GRANULAR BACKFILL (CU YD)	44201717 CLASS D PATCHES TYPE II 6 INCH (SQ YD)
RT 789+56.00 TR 113A (2950N)	38.00	1.00	1.00		38.00	2.00		2.00	25.33
RT 894+84.00 TR 438 (1950E)	34.00	1.00	1.00	34.00			2.00	3.69	25.02
RT 1001+26.60 TR 484A (2151E)	32.00	1.00	1.00		32.00	2.00		1.39	16.62
TOTAL =									
USE =									
	104.00	3.00	3.00	34.00	70.00	4.00	2.00	7.08	66.97
	104.00	3.00	3.00	34.00	70.00	4.00	2.00	7.00	67.00
	(FOOT)	(EACH)	(EACH)	(FOOT)	(FOOT)	(EACH)	(EACH)	(CU YD)	(SQ YD)