ROUTE: US6(200' E. of HOUBOLT RD. TO EMPRESS DR.)

PCC PAVT ENDS 200' +/- E. OF HOUBOLT RD.

CROSS STREETS FROM	TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	PAVT MARKING 6"	RAISED REFL PAVT MKS
488' E. OF PCC PAVT	601' E. OF PCC PAVT	EB	1/2	4	113	452	50	50							
1,407'E. OF PCC PAVT	2,197'E. OF PCC PAVT	EB	1	14	790	11060	1229	1229							
3,292'E. OF PCC PAVT	3,199'E. OF PCC PAVT	WB	1	4	93	372	41	41							
3,290'E. OF PCC PAVT	3,195'E. OF PCC PAVT	WB	1	4	95	380	42	42							
2,990'E. OF PCC PAVT	2,864'E. OF PCC PAVT	WB	1	4	26	104	12			12					
2,904'E. OF PCC PAVT	2,798'E. OF PCC PAVT	WB	1	4	106	424	47	47							
2,610'E. OF PCC PAVT	2,431'E. OF PCC PAVT	WB	1	4	179	716	80	80							
2,498'E. OF PCC PAVT	2,438'E. OF PCC PAVT	WB	1	4	60	240	27	27							
2,200'E. OF PCC PAVT	1,804'E. OF PCC PAVT	WB	1	4	396	1584	176	176							
2,011'E. OF PCC PAVT	1,815'E. OF PCC PAVT	WB	1	4	196	784	87	87							
1,285'E. OF PCC PAVT	1,251'E. OF PCC PAVT	WB	1	4	34	136	15			15					
1,230'E. OF PCC PAVT	914'E. OF PCC PAVT	WB	1	4	316	1264	140	140							
TOTALS:							1946 SY	1920 SY		27 SY			2880 FT	500 FT	28 EACH

ROUTE: US6(WALNUT ST. TO BRIGGS ST.)

800 LF FROM BRIGGS ST. TO LIND ST.

CROSS STREETS FROM	TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
104' E. of BRIGGS ST.	130' E. of BRIGGS ST.	WB	1	6	26	156	17				17			
407' E. of BRIGGS ST.	430' E. of BRIGGS ST.	WB	1	4	23	92	10			10				
MAPLECREST ST.	MAPLECREST ST.	WB	1	4	25	100	11			11				
601' E. of BRIGGS ST.	623' E. of BRIGGS ST.	WB	1	4	22	88	10			10				
707' E. of BRIGGS ST.	LIND ST.	WB	1	4	102	408	45	45						
707' E. of BRIGGS ST.	LIND ST.	EB	1	4	102	408	45	45						
MAPLECREST ST.	MAPLECREST ST.	EB	1	12	52	624	69	69						
*****HMA SURFACE POSSIBLY CONTAINS SLAG*****														
TOTALS:							208 SY	159 SY		31 SY	17 SY		400 FT	8 EACH

FILE NAME = c:\projects\d136308\design_aa.dgn	USER NAME = smithkl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/14/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
US 6

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-012 PP	WILL	33	6

CONTRACT NO. 60E38

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

...\projects\d136308\design_aa.dgn 3/14/2008 9:38:05 AM User=smithkl