

ROUTE: IL 50 / CICERO (GOVERNORS HWY TO COUNTY LINE RD)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
.3 Miles South of Dralle		SB	2	12	20	240	27				27			
.6 Miles South of Dralle		SB	2	2	3	6	1		1					
10' South of Horner Ave		SB	2	2	2	4	1		1					
.1 Miles South of Horner		SB	2	12	40	480	53	53						
.1 Miles South of Horner		SB	2	2	2	4	1		1					
At Monee Manhattan Rd		SB	2	3	8	24	3		3					
2 Miles South of Monee Manhattan Rd		SB	2	4	10	40	4		4					
2 Miles South of Monee Manhattan Rd		SB	2	2	2	4	1		1					
3 Miles South of Monee Manhattan Rd		SB	2	2	2	4	1		1					
4 Miles South of Monee Manhattan Rd		SB	2	4	2	8	1		1					
.1 Miles South of Egyptian		SB	2	3	500	1500	167	167						
2 Miles South of Egyptian		SB	1	12	10	120	13			12				
At Watson Dr		SB	2	3	150	450	50	50						
.1 Miles South of Watson Dr		SB	1	12	2	24	3		2					
5 Miles South of Watson Dr		SB	1&2	14	500	7000	778	778						
2 Miles South of Pauly Rd		SB	2	5	10	50	6			6				
At Offner Rd		SB	1&2	24	10	240	27				27			
At North Peotone Rd		SB	2	2	2	4	1		1					
.3 Miles South of North Peotone Rd		SB	2	2	2	4	1		1					
.8 Miles South of North Peotone Rd		SB	2	2	2	4	1		1					
.9 Miles South of North Peotone Rd		SB	2	3	65	195	22	22						
.1 Miles South of South St		SB	2	4	100	400	44	44						
At 5th St		SB	2	4	25	100	11			11				
.3 Miles South of Wilmington Rd		SB	2	3	12	36	4		4					
.5 Miles South of Wilmington Rd		SB	2	2	100	200	22	22						
.7 Miles South of Wilmington Rd		SB	2	2	4	8	1		1					
1 Mile South of Wilmington Rd		SB	2	2	2	4	1		1					
.1 Miles South of Kennedy		SB	2	2	8	16	2		2					
.1 Miles South of Kennedy		SB	2	12	10	120	13			13				
2 Miles South of Kennedy		SB	1	2	6	12	1		1					
At Rathje Rd		SB	2	2	3	6	1		1					
.1 Miles South of Rathje		SB	1	3	70	210	23	23						
.1 Miles North of County Line Rd		NB	2	2	2	4	1		1					
.1 Miles North of County Line Rd		NB	J	2	8	16	2		2					
.1 Miles North of County Line Rd		NB	2	3	20	60	7			7				
.1 Miles North of County Line Rd		NB	1	2	50	100	11	11						
.2 Miles North of County Line Rd		NB	1	2	2	4	1		1					
.2 Miles North of County Line Rd		NB	1	2	300	600	67	67						
.2 Miles North of County Line Rd		NB	2	3	50	150	17	17						
.4 Miles North of County Line Rd		NB	1	4	8	32	4			4				
.5 Miles North of County Line Rd		NB	2	6	85	510	57	57						
.5 Miles North of County Line Rd		NB	2	3	2	6	1		1					
.5 Miles North of County Line Rd		NB	2	2	8	16	2		2					
.2 Miles North of Rathje		NB	2	2	2	4	1		1					
.3 Miles North of Rathje		NB	2	2	2	4	1		1					
At Beecher Rd		NB	2	2	2	4	1		1					
.1 Miles North of Peotone Rd		NB	1	2	2	4	1		1					
.1 Miles North of Peotone Rd		NB	J	2	8	16	2		2					
.1 Miles North of Peotone Rd		NB	J	2	2	4	1		1					
.3 Miles North of Peotone Rd		NB	J	2	2	4	1		1					
At Eagle Lake Rd		NB	2	3	3	9	1		1					
.3 Miles North of Eagle Lake Rd		NB	2	5	10	50	6			6				
.1 Miles North of Offner Rd		NB	2	4	4	16	2		2					
.1 Miles North of Offner Rd		NB	J	3	50	150	17	17						
.1 Miles North of Offner Rd		NB	2	12	20	240	27				27			
.2 Miles North of Offner Rd		NB	2	3	10	30	3		3					
.7 Miles North of Offner Rd		NB	2	6	3	18	2		2					
.8 Miles North of Offner Rd		NB	1&2	24	118	2832	315	315						
100' South of Pauly Rd		NB	1&2	24	20	480	53				53			
.1 Miles North of Pauly Rd		NB	2	3	250	750	83	83						
.2 Miles North of Pauly Rd		NB	1	2	8	16	2		2					
.6 Miles North of Pauly Rd		NB	2	2	150	300	33	33						
At Watson Rd		NB	2	2	2	4	1		1					
At Wayne Stassen Way		NB	2	2	2	4	1		1					
At Wayne Stassen Way		NB	1&2	18	10	180	20				20			
.5 Miles North of Monee Manhattan Rd		NB	1	10	12	120	13			13				
.2 Miles North of Bond St		NB	2	2	300	600	67	67						
.2 Miles North of Bond St		NB	1	12	20	240	27				27			
.2 Miles North of Bond St		NB	J	2	50	100	11	11						
.3 Miles North of Bond St		NB	2	3	50	150	17	17						
.4 Miles North of Bond St		NB	J	3	8	24	3		3					

TOTALS:

2163 1854 58 72 128 53 3834 38
SY SY SY SY SY SY FT EACH

FILE NAME =
c:\projects\136308\design_aa.dgn

USER NAME = smthkl
DESIGNED -
DRAWN -
PLOT SCALE = 100.0000' / IN.
PLOT DATE = 3/14/2008

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 50 (CICERO AVE.)

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-012 PP	WILL	33	13
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60E38	