



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 5, 2016

SUBJECT: FAU 8190 (North Main Street)
Section 15-00121-03-PV (Jacksonville)
Morgan County
Contract No. 93670
Item 105
April 22, 2016 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans and/or the proposal. This addendum involves revised, added and/or deleted material.

- 1. Revised Plan Sheet 2.**
- 2. Revised page 2 of the Special Provisions Table of Contents**
- 3. Revised page 33 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.
Acting Bureau Chief of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger, P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

	<u>Page</u>
Pavement Patching	22
Removal of Unclassified Material	22
Storm Sewer Connections	22
Existing Drain Pipes	22
Debris	22 - 23
Existing Frames and Grates	23
Temporary Drainage into Proposed Drainage Structures	23
Fire Hydrants to be Removed	23
Concrete Sidewalk Finishing	23 - 24
Street Lighting Assembly Complete	24 – 26
Sodding	26 - 29
Telescoping Steel Sign Support (Special)	29 - 30
Staging of Water Main Hydrostatic Test	30
Water Main to be Abandoned	30 - 31
Combination Concrete Curb and Gutter Abutting Existing Pavement	31
Concrete Curb Type B (Special)	31 - 32
Concrete Median Surface, 4 Inch	32
Domestic Water Service Boxes to be Adjusted	32
QC/QA of Concrete Mixtures – Applicable Items	32
Aggregate Surface Course, Type B	33
Existing Signs To Be Removed	33

AGGREGATE SURFACE COURSE, TYPE B:

This work shall consist of the construction of aggregate entrances and areas adjacent to curb 8" in thickness, using the material specified and as located in the plans and directed by the Engineer. This work shall be completed in accordance with Section 402 of the Standard Specifications.

Basis of Payment: This work shall be paid for at the unit cost per Ton for AGGREGATE SURFACE COURSE, TYPE B, which price shall include all labor, material, and equipment necessary to complete the work to the satisfaction of the Engineer.

EXISTING SIGNS TO BE REMOVED:

This work shall consist of the removal of existing sign panels, sign panel assemblies, and supports that conflict with the final signing as shown in the plans and as directed by the Engineer. This work shall be completed in accordance with Section 724 of the Standard Specifications. Sign panels removed shall become the property of the City of Jacksonville.

This work shall not be paid for separately, but considered included in the cost of Sign Panels to be erected and no additional compensation shall be allowed.

STORM SEWER REMOVAL:

This work shall consist of the removal of existing storm sewers as shown in the plans, and as directed by the Engineer. This work shall be completed in accordance with Section 551 of the Standard Specifications and as directed by the Engineer.

Trench backfill for storm sewer removal will not be paid for separately, but will be included in the cost for the associated Storm Sewer Removal. Additionally, pavement patches shall be constructed at the locations of the Storm Sewer Removal in accordance with the applicable specifications for Class C Patches, which price shall also be included in the cost for Storm Sewer Removal.

Basis of Payment: This work shall be paid for at the unit cost per Foot for STORM SEWER REMOVAL, which price shall include all labor, material, and equipment