

| PAY CODE | DESCRIPTION  | UNIT   | TOTAL QUANTITY | 80% FED, 20% STATE     |                         |
|----------|--|--------|----------------|------------------------|-------------------------|
|          |  |        |                | SALINE COUNTY          |                         |
|          |  |        |                | SEC (2-B)-1<br>X028-2A | SEC (2B-1)-1<br>X028-2A |
| 20100500 | TREE REMOVAL, ACRES  | ACRE   | 0.5            | 0.25                   | 0.25                    |
| 20200100 | EARTH EXCAVATION   | CU YD  | 6735           | 30.5                   | 6430                    |
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL                          | CU YD  | 310            | 0                      | 310                     |
| 20300100 | CHANNEL EXCAVATION   | CU YD  | 305            | 140                    | 165                     |
| 20700220 | POROUS GRANULAR EMBANKMENT   | CU YD  | 1085           | 855                    | 230                     |
| 21400100 | GRADING AND SHAPING DITCHES  | FOOT   | 41             | 0                      | 41                      |
| 25001010 | SEEDING, CLASS 2 (MODIFIED)  | ACRE   | 2.00           | 0.5                    | 1.50                    |
| 25000350 | SEEDING, CLASS 7   | ACRE   | 2.00           | 0.5                    | 1.50                    |
| 25000400 | NITROGEN FERTILIZER NUTRIENT   | POUND  | 297            | 47                     | 250                     |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT                                       | POUND  | 222            | 35                     | 187                     |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT  | POUND  | 222            | 35                     | 187                     |
| 25000700 | AGRICULTURAL GROUND LIMESTONE  | TON    | 3.8            | 0.7                    | 3.1                     |
| 25100115 | MULCH, METHOD 2  | ACRE   | 4.25           | 0.75                   | 3.50                    |
| 25100630 | EROSION CONTROL BLANKET  | SQ YD  | 1490           | 260                    | 1238                    |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING                                    | POUND  | 186            | 30                     | 156                     |
| 28000300 | TEMPORARY DITCH CHECKS   | EACH   | 6              | 0                      | 6                       |
| 28000400 | PERIMETER EROSION BARRIER  | FOOT   | 2447           | 843                    | 1604                    |
| 28000500 | INLET AND PIPE PROTECTION  | EACH   | 1              | 0                      | 1                       |
| 28100107 | STONE RIPRAP, CLASS A4   | SQ YD  | 32             | 0                      | 32                      |
| 28100109 | STONE RIPRAP, CLASS A5   | SQ YD  | 748            | 409                    | 339                     |
| 28200100 | FILTER FABRIC FOR USE WITH RIPRAP                                    | SQ YD  | 748            | 409                    | 339                     |
| 35100100 | AGGREGATE BASE COURSE, TYPE A  | TON    | 701            | 0                      | 701                     |
| 35300410 | PORTLAND CEMENT CONCRETE BASE COURSE, 9 1/2"                         | SQ YD  | 363            | 235                    | 128                     |
| 35600500 | BITUMINOUS CONCRETE BASE COURSE WIDENING, 10"                        | SQ YD  | 79             | 44                     | 35                      |
| 40200000 | AGGREGATE SURFACE COURSE, TYPE B                                     | TON    | 84             | 30                     | 54                      |
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT)                                    | GALLON | 1365           | 396                    | 969                     |
| 42001200 | PAVEMENT FABRIC  | SQ YD  | 363            | 235                    | 128                     |
| 44000035 | BITUMINOUS SURFACE REMOVAL   | SQ YD  | 141            | 0                      | 141                     |
| 44000100 | PAVEMENT REMOVAL   | SQ YD  | 442            | 279                    | 163                     |
| 48101200 | AGGREGATE SHOULDERS, TYPE B  | TON    | 159            | 0                      | 159                     |
| 48202000 | BITUMINOUS SHOULDERS, SUPERPAVE, 10"                                 | SQ YD  | 1986           | 1076                   | 910                     |
| 50100100 | REMOVAL OF EXISTING STRUCTURES                                       | EACH   | 2              | 1                      | 1                       |
| 50105220 | PIPE CULVERT REMOVAL   | FOOT   | 155            | 0                      | 155                     |
| 50800105 | REINFORCEMENT BARS   | POUND  | 62010          | 38610                  | 23400                   |
| 51205200 | TEMPORARY SHEET PILING   | SQ FT  | 1899           | 1053                   | 846                     |
| 51401600 | TEMPORARY BRIDGE RAIL  | FOOT   | 45             | 22                     | 23                      |
| 51500100 | NAME PLATES  | EACH   | 2              | 1                      | 1                       |
| 54003000 | CONCRETE BOX CULVERTS  | CU YD  | 337.5          | 210.5                  | 127.0                   |
| 54200640 | PIPE CULVERTS, TYPE I, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15" | FOOT   | 88             | 0                      | 88                      |
| 54200661 | PIPE CULVERTS, TYPE I, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 36" | FOOT   | 29             | 29                     | 0                       |
| 54200217 | PIPE CULVERTS, CLASS A, TYPE 1, 12"                                  | FOOT   | 28             | 0                      | 28                      |
| 54200223 | PIPE CULVERTS, CLASS A, TYPE 1, 18"                                  | FOOT   | 40             | 0                      | 40                      |
| 54200235 | PIPE CULVERTS, CLASS A, TYPE 1, 30"                                  | FOOT   | 52             | 0                      | 52                      |

| PAY CODE   | DESCRIPTION  | UNIT   | TOTAL QUANTITY | 80% FED, 20% STATE     |                         |
|------------|--|--------|----------------|------------------------|-------------------------|
|            |  |        |                | SALINE COUNTY          |                         |
|            |  |        |                | SEC (2-B)-1<br>X028-2A | SEC (2B-1)-1<br>X028-2A |
| 54213657   | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"                | EACH   | 2              | 0                      | 2                       |
| 54213663   | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"                | EACH   | 2              | 0                      | 2                       |
| 54213675   | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"                | EACH   | 2              | 0                      | 2                       |
| 54215550   | METAL END SECTION, 15"   | EACH   | 4              | 0                      | 4                       |
| 60600095   | CLASS SI CONCRETE (OUTLET)   | CU YD  | 0.3            | 0                      | 0.3                     |
| 60602500   | CONCRETE GUTTER, TYPE A  | FOOT   | 157            | 0                      | 157                     |
| *63000000  | STEEL PLATE BEAM GUARD RAIL, TYPE A                                | FOOT   | 744            | 369                    | 375                     |
| *63000025  | STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES                | FOOT   | 132            | 69                     | 63                      |
| *LR631020  | TRAFFIC BARRIER TERMINAL, TYPE 1                                   | EACH   | 4              | 0                      | 4                       |
| *63100167  | TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)                 | EACH   | 1              | 0                      | 1                       |
| *63100045  | TRAFFIC BARRIER TERMINAL, TYPE 2                                   | EACH   | 2              | 2                      | 0                       |
| *63200310  | GUARDRAIL REMOVAL  | FOOT   | 83             | 0                      | 83                      |
| 63300205   | REM AND REIN OF EX STEEL PLATE BEAM GUARD RAIL, TYPE A             | FOOT   | 287.5          | 137.5                  | 150                     |
| 70500690   | TEMPORARY TRAFFIC BARRIER TERMINAL TYPE II                         | EACH   | 1              | 2                      | 3                       |
| 67000400   | ENGINEER'S FIELD OFFICE, TYPE A                                    | CAL MO | 6              | 3                      | 3                       |
| 67100100   | MOBILIZATION   | L SUM  | 1              | 0.5                    | 0.5                     |
| 70100460   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306                    | L SUM  | 1              | 0                      | 1                       |
| 70100500   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326                    | L SUM  | 1              | 0.5                    | 0.5                     |
| 70101205   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)          | EACH   | 2              | 1                      | 1                       |
| 70106500   | TEMPORARY BRIDGE TRAFFIC SIGNALS                                   | EACH   | 2              | 1                      | 1                       |
| 70106700   | TEMPORARY RUMBLE STRIP   | EACH   | 24             | 12                     | 12                      |
| 70300220   | TEMPORARY PAVEMENT MARKING - LINE 4 INCH                           | FOOT   | 846            | 469                    | 377                     |
| 70300280   | TEMPORARY PAVEMENT MARKING - LINE 24 INCH                          | FOOT   | 72             | 36                     | 36                      |
| 70301000   | WORK ZONE PAVEMENT MARKING REMOVAL                                 | SQ FT  | 325            | 171                    | 154                     |
| 70400100   | TEMPORARY CONCRETE BARRIER   | FOOT   | 600            | 340                    | 260                     |
| 70400200   | RELOCATE TEMPORARY CONCRETE BARRIER                                | FOOT   | 310            | 180                    | 130                     |
| *78001110  | PAINT PAVEMENT MARKING-LINE 4"                                     | FOOT   | 4931           | 2568                   | 2363                    |
| *78001180  | PAINT PAVEMENT MARKING-LINE 24"                                    | FOOT   | 22             | 0                      | 22                      |
| 78200410   | GUARDRAIL MARKERS, TYPE A  | EACH   | 22             | 10                     | 12                      |
| 78200520   | BARRIER WALL MARKERS, TYPE B                                       | EACH   | 8              | 4                      | 4                       |
| X4066418   | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N90        | TON    | 198            | 20                     | 178                     |
| X4066618   | BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19, N90           | TON    | 168            | 0                      | 168                     |
| X6330103   | REMOVE & RE-ERECT TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL, TANGENT | EACH   | 7              | 4                      | 3                       |
| Z0002600   | BAR SPLICERS   | EACH   | 257            | 135                    | 122                     |
| ⊙ Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3       | EACH   | 4              | 2                      | 2                       |
| ⊙ Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3      | EACH   | 4              | 2                      | 2                       |

\* SPECIALTY ITEM ⊙ SFTY-3N

|             |         |        |              |           |
|-------------|---------|--------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 778         |         | SALINE | 74           | 3         |

FED. ROAD DIST. NO. 9 ILLINOIS FED. AID PROJECT  
 (2-B)-1 & (2B-1)-1

| REVISIONS |      |
|-----------|------|
| NAME      | DATE |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAP ROUTE 778 (IL 34)  
 SECS. (2-B)-1 & (2B-1)-1, SALINE COUNTY  
**COMBINED SUMMARY OF QUANTITIES**  
 SCALE: VERT. \_\_\_\_\_ HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_ CHECKED BY \_\_\_\_\_

11/17/2003 10:30 AM