

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
778	(2-B)-1	SALINE	74	6
FED. ROAD DIST. NO. 9 ILLINOIS FED. AID PROJECT				

GUARD RAIL SCHEDULE							
LOCATION		63000000 STEEL PLATE BEAM GUARD RAIL TYPE A (FOOT)	63000025 STEEL PLATE BEAM GUARD RAIL ATTACHED TO STRUCTURES (FOOT)	63300205 REM & REIN OF EXIST SPBGR TYPE A (FOOT)	63100045 TRAFFIC BARRIER TERMINAL TYPE 2 (EACH)	78200410 GUARD RAIL MARKERS, TYPE A (EACH)	X6330103 REM & RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT (EACH)
STATION	TO STATION						
STAGE I							
435+44.5 RT	435+82.0 RT		38				
435+00 RT	435+50 RT			50.0			
434+13 RT	434+57 RT				2		
434+50 RT	435+00 RT						1
435+75 RT	436+25 RT						1
434+57 RT	436+44.5 RT	88					
433+63 RT	436+94.5 RT					4	
STAGE II							
433+68 LT	438+55.5 LT					6	
435+49.25 LT	435+80.5 LT		31				
435+38.5 LT	435+50 LT			13			
435+75 LT	436+50 LT			75			
434+88.5 LT	435+38.5 LT						1
436+50 LT	437+00 LT						1
434+18 LT	438+05.5 LT	269					
<b>TOTAL</b>		357	69	138	2	10	4
PREPARED BY: KMN - CHECKED BY:							

NOTE: COST OF REMOVAL OF EXISTING GUARDRAIL TO FIRST POST PAST BRIDGE IS INCLUDED IN COST OF 'REMOVAL OF EXISTING STRUCTURES'

BRIDGE RAIL / CONCRETE BARRIER SCHEDULE					
LOCATION	51401600 TEMPORARY BRIDGE RAIL (FOOT)	70400100 TEMPORARY CONCRETE BARRIER (FOOT)	70400200 RELOCATE TEMPORARY CONCRETE BARRIERS (FOOT)	70500690 TEMPORARY TRAFFIC BARRIER TERMINAL TYPE 11 (EACH)	78200520 BARRIER * WALL MARKERS TYPE B (EACH)
STAGE					
I	22	180		2	4
II		160	180		0
<b>TOTAL</b>					
	22	340	180	2	4
PREPARED BY: KMN - CHECKED BY:					

\* STAGE I MARKERS TO BE REMOVED & REUSED ON STAGE II BARRIER. STAGE II QUANTITY IS FOR ADDITIONAL MARKERS NEEDED.

PAVEMENT MARKING / PAVEMENT MARKING REMOVAL SCHEDULE						
LOCATION		70300220 TEMPORARY PAVEMENT MARKING 4' LINE - WHITE (FOOT)	70300280 TEMPORARY PAVEMENT MARKING 24' LINE - WHITE (FOOT)	70301000 WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	78001100 PAINT PAVEMENT MARKING 4' LINE - WHITE (FOOT)	PAINT PAVEMENT MARKING 4' LINE - YELLOW (FOOT)
STATION	TO STATION					
STAGE I						
434+77.5 LT	436+48.5 LT	171				
432+43 RT	---		12	24		
439+09 LT	---		12			
432+96 RT	438+00 RT				504	
STAGE II						
433+83 RT	436+81 RT	298		99		
439+09 LT	---			24		
431+51 RT	---		12	24		
433+34 LT	439+00 LT				566	
431+51 C	439+00 C					1498
<b>SUBTOTAL</b>				1070		1498
<b>TOTAL</b>		469	36	171	2568	
PREPARED BY: KMN - CHECKED BY:						

REMOVAL SCHEDULE			
LOCATION		44000035 BITUMINOUS SURFACE REMOVAL (SQ YD)	44000100 PAVEMENT REMOVAL (SQ YD)
STATION	TO STATION		
STAGE I			
435+20 RT	436+08 RT		113
STAGE II			
435+20 LT	436+08 LT		122
434+77.5 LT	436+48.5 LT		44
<b>TOTAL</b>			
		0	279
PREPARED BY: KMN - CHECKED BY:			

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAP ROUTE 778 (IL 34) SEC. (2-B)-1, SALINE COUNTY
NAME	DATE	
		<b>SCHEDULE OF QUANTITIES</b>  VERT. SCALE:                      DRAWN BY HORIZ.                              CHECKED BY DATE

11/15/2004 10:00 AM