

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
778	(2B-1)-1	SALINE	74	30
FED. ROAD DIST. NO. 9 ILLINOIS FED. AID PROJECT				

PAVEMENT SCHEDULE												
LOCATION			35100100	35300410	35600500	40200900	40600100	420001200	48101200	48202800	X4066418	X4066618
			AGGREGATE BASE COURSE TYPE A	PORTLAND CEMENT CONCRETE BASE COURSE, 9 1/2"	BITUMINOUS CONCRETE BASE COURSE WIDENING, 10"	AGGREGATE SURFACE COURSE, TYPE B	BITUMINOUS MATERIALS (PR CT)	PAVEMENT FABRIC	AGGREGATE SHOULDERS TYPE B	BITUMINOUS SHOULDERS SUPERPAVE, 10"	BIT CONC SURFACE CSE SUPERPAVE MIX "C", N90	BIT CONC BINDER CSE SUPERPAVE IL-19, N90
STATION	TO	STATION	(TON)	(SQ YD)	(SQ YD)	(TON)	(GALLON)	(SQ YD)	(TON)	(SQ YD)	(TON)	(TON)
STAGE I												
20+20		27+60 DENEAL	701				606				160	160
441+16 LT		441+64		56			5	56			5	
440+74.5 RT		442+60.5			35							
25+03 LT		25+45 DENEAL				16						
23+60.5 LT		24+05.5 DENEAL				33						
20+45		27+60 DENEAL							159			
439+00 LT		444+59					188			536		
STAGE II												
441+16 RT		441+64		72			7	72			6	
438+00 RT		443+39.5					163				374	
438+77 RT		439+43									7	8
MISC.						5						
TOTAL			701	128	35	54	969	128	159	910	178	168

PREPARED BY: KMN - CHECKED BY:

RIPRAP SCHEDULE					
LOCATION			28100107	28100109	28200100
			STONE RIPRAP CLASS A4	STONE RIPRAP CLASS A5	FILTER FABRIC FOR USE WITH RIPRAP (SQ YD)
STATION	TO	STATION	(SQ YD)	(SQ YD)	(SQ YD)
STAGE I					
441+10.4 LT		441+70.8		196	196
20+68		20+84 DENEAL	32		32
STAGE II					
441+10.4 RT		441+70.8		143	167
TOTAL			32	339	395

PREPARED BY: KMN - CHECKED BY:

DRAINAGE STRUCTURE SCHEDULE												
LOCATION			542A0217	542A0223	542A0235	54200640	54213657	54213660	54213675	54215558	60600295	60602500
			PIPE CULVERT CLASS A, TY 1, 12"	PIPE CULVERT CLASS A, TY 1, 18"	PIPE CULVERT CLASS A, TY 1, 30"	PIPE CULVERT TY 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE, 15" (FOOT)	PRC END SECTION 12"	PRC END SECTION 18"	PRC END SECTION 30"	METAL END SECTION 15"	CLASS SI CONC	CONC GUTTER TY A
STATION	TO	STATION	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(CU YD)	(FOOT)
STAGE I												
26+88 RT		27+16 DENEAL	28				2					
20+70		---		40				2				
22+75		---			52				2			
23+60 LT		24+00				40				2		
STAGE II												
23+56 RT		24+04				48						
443+28 LT		444+59										157
443+28 LT		---								2	0.3	
TOTAL			28	40	52	88	2	2	2	4	0.3	157

PREPARED BY: KMN - CHECKED BY:

EARTHWORK SCHEDULE				
		IL RTE 34	DENEAL ROAD	TOTAL
EARTH EXCAVATION	20200100	1295	5135	6430
CHANNEL EXCAVATION (SUITABLE)	20300100	125	0	125
CHANNEL EXCAVATION (UNSUITABLE)	20300100	40	0	40
STRUCTURE EXCAVATION (SUITABLE)	(NOT A PAY ITEM)	260	0	260
STRUCTURE EXCAVATION (UNSUITABLE)	(NOT A PAY ITEM)	115	0	115
TOTAL SUITABLE EARTH, CHANNEL & STRUCTURE EXCAVATION	(NOT A PAY ITEM)	1680	5135	6815
TOTAL SUITABLE EXCAVATION ADJUSTED FOR 25% SHRINKAGE	(NOT A PAY ITEM)	1260	3850	5110
EMBANKMENT	(NOT A PAY ITEM)	190	440	630
NET FILL (LESS SUITABLE EXCAVATION)	(NOT A PAY ITEM)	0	0	0
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	20201200	0	310	310
POROUS GRANULAR EMBANKMENT, CA-10	20700200	75	0	75
POROUS GRANULAR EMBANKMENT, CA-7 OR CA-11	20700200	155	0	155

NOTE: ITEMS SHOWN AS 'NOT A PAY ITEM' ARE FOR INFORMATION ONLY

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAP ROUTE 778 (IL 34) SEC. (2B-1)-1, SALINE COUNTY
NAME	DATE	
		<p>SCHEDULE OF QUANTITIES</p> <p>SCALE: VERT. _____ HORIZ. _____</p> <p>DATE: _____ DRAWN BY: _____ CHECKED BY: _____</p>