

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
778	(2B-1)-1	SALINE	74	31
FED. ROAD DIST. NO. 9 ILLINOIS FED. AID PROJECT				

GUARD RAIL SCHEDULE										
LOCATION			63200310 GUARD RAIL REMOVAL	63000000 STEEL PLATE BEAM GUARD RAIL TYPE A	63000225 STEEL PLATE BEAM GUARD RAIL ATTACHED TO STRUCTURES	63300205 REM & REIN OF EXIST SPBGR TYPE A	X6330103 REM & RE-ERECT TRAFFIC BARRIER TERM, TYPE 1 SPECIAL, TANGENT	LR631020 TRAFFIC BARRIER TERMINAL TYPE 1	78200410 GUARD RAIL MARKERS, TYPE A	
STATION	TO	STATION	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	
STAGE I										
441+62	LT	441+73	75		31					
441+26.75	LT	441+58								
440+84	LT	441+34					1			
443+63	LT	444+13						1		
442+59	LT	443+63						2		
440+20.5	LT	443+63		244						
439+71.5	LT	444+13							6	
STAGE II										
441+24.25	RT	441+55.5			32					
439+82	RT	441+38	6			150				
441+63	RT	441+65	2				1			
439+32	RT	439+82					1			
441+65	RT	442+15								
438+77	RT	439+43						2		
439+43	RT	442+55.5		132						
439+27	RT	443+05.5							6	
TOTAL			83	375	63	150	3	1	4	12

PREPARED BY: KMN - CHECKED BY:

REMOVAL SCHEDULE					
LOCATION			44000035 BIT SURF REMOVAL	44000100 PAVEMENT REMOVAL	50105220 PIPE CULVERT REMOVAL
STATION	TO	STATION	(SQ YD)	(SQ YD)	(FOOT)
STAGE I					
441+16	LT	441+64		61	
27+40		27+60	44		
441+61	LT	442+21			60
22+47	LT	22+67			20
23+65	LT	24+00			35
22+81	LT	22+89			40
STAGE II					
441+16	RT	441+64		67	
440+74.5	RT	442+60.5		35	
438+77	RT	439+43	97		
TOTAL			141	163	155

PREPARED BY: KMN - CHECKED BY:

NOTE: COST OF REMOVAL OF EXISTING GUARDRAIL TO FIRST POST PAST BRIDGE IS INCLUDED IN COST OF "REMOVAL OF EXISTING STRUCTURES"

BRIDGE RAIL / CONCRETE BARRIER SCHEDULE						
LOCATION		51401600 TEMPORARY BRIDGE RAIL	63300775 TEMPORARY TERMINAL SECTION	70400100 TEMPORARY CONCRETE BARRIER	70400200 RELOCATE TEMPORARY CONCRETE BARRIERS	78200520 BARRIER * WALL MARKERS TYPE B
STAGE	(FOOT)	(EACH)	(FOOT)	(FOOT)	(FOOT)	(EACH)
I	23	2	130			4
II			130	130		0
TOTAL		23	2	260	130	4

PREPARED BY: KMN - CHECKED BY:

* STAGE I MARKERS TO BE REMOVED & REUSED ON STAGE II BARRIER.
STAGE II QUANTITY IS FOR ADDITIONAL MARKERS NEEDED.

PAVEMENT MARKING / PAVEMENT MARKING REMOVAL SCHEDULE							
LOCATION			70300220 TEMPORARY PAVEMENT MARKING 4' LINE - WHITE (FOOT)	70300260 TEMPORARY PAVEMENT MARKING 24' LINE - WHITE (FOOT)	70301000 WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	78001100 PAINT PAVEMENT MARKING 4' LINE - WHITE (FOOT)	78001180 PAINT PAVEMENT MARKING 4' LINE - YELLOW (FOOT)
STATION	TO	STATION	(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)
STAGE I							
440,74.5	LT	442+06.5	132				
438+40	LT	---		12	24		
445+32	RT	---		12			
439+00	LT	444+59				559	
20+30	LT	---					11
STAGE II							
440+35	RT	442+80	245		82		
445+32	RT	---			24		
437+14	LT	---		12	24		
438+00	RT	443+39.5				540	
439+00	C	445+32					1264
439+10	RT	439+21					
SUBTOTAL						1099	1264
TOTAL			377	36	154	2363	11

PREPARED BY: KMN - CHECKED BY:

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAP ROUTE 778 (IL 34) SEC. (2B-1)-1, SALINE COUNTY
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p>SCALE: VERT. DRAWN BY HORIZ. CHECKED BY</p>