F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
322	4-I	JACKSON	26	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 98807

SHEET 2 OF 2

		STP-RURAL 80% FEDERAL / 20% STATE JACKSON COUNTY		
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY
	CONSTRUCTION TYPE CODE			1000-1A
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	80	80
54213450	END SECTIONS 15"	EACH	8	8
67000400	ENGINEER'S FIELD OFFICE, TYPE A.	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	176	176
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	37	37
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9130	9130
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	802	802
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	22	22
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	59	59
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	37	37
78000600	THERMOPLASTIC PAVEMENT MARKING LINE 12"	FOOT	802	802
78000650	THERMOPLASTIC PAVEMENT MARKING LINE 24"	FOOT	22	22
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	9130	9130
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	35	35
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	15	15

Thu Feb 5 14:23:30 2004
c:\pr\objects\d902503\d902503msum32 LV=1:63

SUMMARY OF QUANTITIES