

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	4-1	JACKSON	26	7
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 98807				

TREE REMOVAL SCHEDULE

LOCATION STATION	OFFSET FROM EOP FEET	6 TO 15 INCHES UNITS	OVER 15 INCHES UNITS
760+82	RT 35'		22
761+75	RT. 22.4		37
762+50	RT. 22.7		29
762+75	RT. 22.7		32
765+26	RT. 18'	13	22
771+64	LT. 24'	22	19
771+68	LT. 24'		19
771+79	LT. 29'		69
TOTALS		35	249

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE *	EMBANKMENT *	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) *
STATION TO STATION	CU YD	CU YD	CU YD	CU YD
U. S. 51				
757+00 - 766+00	2296	1607	21	+1586
766+00 - 773+50	980	686	1152	-466
TOTALS	3276	2293	1173	1120

\* FOR INFORMATION ONLY  
A 30% SHRINKAGE FACTOR HAS BEEN APPLIED TO EARTH EXCAVATION

DRAINAGE SCHEDULE

LOCATION	PIPE CULVERTS CLASS D, TYPE 1 15 INCH	END SECTIONS 15 INCH EACH	PIPE CULVERT REMOVAL
STATION	FOOT		FOOT
758+40 TO 758+60 RT	EXISTING TO REMAIN	2	
760+57 TO 760+81 RT. 34'	24	2	
762+48 TO 762+78 RT. 39'	30	2	
764+10 TO 764+40 RT. 37'	26	2	
767+08.32			30
TOTALS	80	8	30

PAVEMENT AND SHOULDER SCHEDULE

LOCATION	BITUMINOUS SURFACE COURSE SUPERPAVE	BITUMINOUS BINDER COURSE SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE 8"	INCIDENTAL BITUMINOUS SURFACING	AGGREGATE SHOULDERS	SUB-BASE GRANULAR MATERIAL	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	STRIP REFLECTIVE CRACK CONTROL	TEMPORARY RAMP	PCC DRIVEWAY 7 INCH	AGGREGATE SURFACE CSE, TYPE A
STATION TO STATION	TON	TON	SQ YD	TON	TON	TON	GALLON	TON	FOOT	SQ YD	SQ YD	TON
756+32.47									1389	5.5		
757+32 TO 771+41 RT												
756+32.47 TO 758+53 LT			74		25							
756+32.47 TO 772+61.77 RT	289		543				305	5				
756+32.47 TO 772+61.77 LT	208				186							
758+28 TO 770+40 RT (WIDENING)		772				510	220	4				
758+66.32 P.E. RT				4.3			13	.06				9
760+68.92 P.E. RT											40	16
762+64.09 C.E. RT				5.8			17	.08				
764+30.22 P.E. RT				5.5			16	.08				4
767+08 P.E. RT				5.4			16	.08				8
768+03 TO 772+61.77 LT			153		52							
772+61.77										5.5		
SUBTOTALS	497	722	770	21	263	510	587	9.3	1389	11	40	37
UNION STREET	44						47	0.7		77		
SUBTOTALS	44	0	0	0	0	0	47	0.70	0	77	0	0
TOTALS	541	722	770	21	263	510	634	10	1389	88	40	37

EARTHWORK, PAVEMENT & SHOULDER, TREE REMOVAL, AND DRAINAGE SCHEDULES

DATE-TIME  
LOG-SPEC