

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
322	4-1	JACKSON	26	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 98907				

PAVEMENT MARKING SCHEDULE

LOCATION	PAINT			THERMOPLASTIC		
	4 INCH WHITE	4 INCH YELLOW	4 INCH DOUBLE YELLOW	24 INCH WHITE	LETTERS & SYMBOLS WHITE	12 INCH YELLOW
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT
756+32.47 TO 772+61.77	3179.3					
756+32.47 TO 757+52		240				461
764+25 TO 765+40	115					
757+50 TO 764+20			2642			
766+00 TO 771+50			2720			341
764+25					20.8	
764+50					15.6	
771+50 TO 772+61.77		223.5				
UNION STREET		10		22		
TOTALS	3294	474	5362	22	37	802

SEEDING AND EROSION CONTROL SCHEDULE

LOCATION	SEEDING CLASS 1B	SEEDING CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2	EROSION CONTROL BLANKET	TEMPORARY DITCH CHECKS	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	STONE DUMPED RIPRAP CL A3
STATION TO STATION	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE	SQ YD	EACH	POUND	FOOT	EACH	TON
756+52.47 TO 761+80 LT	0.1	0.1	16	12	12	0.2	0.2	375		20			
768+00 TO 772+41.77	0.4	0.4	64	48	48	0.8	0.8	1710	7	80	150		
756+52.47 TO 772+41.77	0.9	0.9	144	108	108	1.8	1.8	4321	3	180	75		
771+00 LT & RT												2	
770+00 TO 771+00 RT													78
TOTAL	1.4	1.4	224	168	168	2.8	2.8	6406	10	280	225	2	78

Thu Feb 5 14:45:58 2004 c:\p\projects\4502503\4502503.mxd LVH:63