

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	5-(2,3)-1,TS-2	JACKSON	94	16
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

### REMOVAL SCHEDULE

LOCATION STATION TO STATION	PAVEMENT REMOVAL	STORM SEWER REMOVAL	REMOVING INLET	CONCRETE HEADWALL REMOVAL	COMBINATION CURB & GUTTER REMOVAL	PAVED SHOULDER REMOVAL	ISLAND REMOVAL	CONCRETE MEDIAN SURFACE REMOVAL	BITUMINOUS SURFACE REMOVAL VAR. DEPTH	BITUMINOUS SURFACE REMOVAL 1 1/2"	CONCRETE REMOVAL	SIDEWALK REMOVAL
	SQ YD	FOOT	EACH	EACH	FOOT	SQ YD	SQ FT	SQ FT	SQ YD	SQ YD	CU YD	SQFT
<b>ILLINOIS 13 (WESTBOUND)</b>												
121+55 TO 126+00									728	1088		
RT 121+91.26 TO 126+00						188						
10+00 TO 17+96.44									2068			
RT 10+00 TO 17+96.44						354						
LT 10+00 TO 17+96.44						708						
LT 134+00 TO 142+19.30						728						
134+00 TO 161+03.66										6609		
LT 142+19.35 TO 142+99.08	300											
LT 142+36				1								
LT 142+36 TO 143+00		64										
LT 142+68			1									
LT 142+78.84 TO 142+95.55							163					
LT 143+59 TO 144+32		73										
LT 143+59.12 TO 144+57.73	350											
LT 143+64.91 TO 143+96.00							384					
RT 143+89 TO 144+25 (MEDIAN NOSE)								93				
LT 144+00			1									
LT 144+32				1								
LT 144+57.74 TO 150+29.22						254						
39.24' RT 146+15.91								4				
LT 146+39.83 (EXT. LEVEE)											2.2	
38.85' RT 146+94.43								4				
LT 147+81.12 TO 150+81.64 LTL	225											
LT 150+29.22 TO 156+02.44						495						
<b>GIANT CITY ROAD (NORTH)</b>												
RT 100+79.57 TO 101+18.83												157
LT 100+87.79 TO 101+18.83												121
LT 101+24.91 TO 142+19.30 (ILL 13)												
RT 101+42.13 TO 144+57.74 (ILL 13)												
						142						
						170						
<b>TOTALS</b>	<b>875</b>	<b>137</b>	<b>2</b>	<b>2</b>	<b>312</b>	<b>2727</b>	<b>547</b>	<b>101</b>	<b>2796</b>	<b>7697</b>	<b>2.2</b>	<b>278</b>