

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAI 57	*	ALEXANDER	17	2
FAP 726				
FED. ROAD DIST. NO. 7	ILLINOIS	PROJECT:		

*D-9 HOAN DETAIL REPAIR FY 04-01

98846

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	COVER SHEET, SIGNATURES
2	INDEX OF SHEETS, STANDARDS, GENERAL NOTES,
3	SUMMARY OF QUANTITIES
4	PLAN VIEW TEMPORARY CONCRETE BARRIER
5	TOTAL BILL OF MATERIAL, GENERAL PLAN AND ELEVATION
6	FRAMING PLAN
7, 8	STIFFENER MODIFICATION DETAILS
9	TYPICAL CONNECTION AT VERTICAL STIFFENER, LOCATIONS b & c
10	TYPICAL CONNECTION AT VERTICAL STIFFENER, LOCATION d
11	REPAIR DETAILS b, c, d
12	REPAIR DETAIL E, SECTION THRU FLOORBEAM
13	CONCRETE REMOVAL AND REPLACEMENT
14	PARAPET AND RAILING DETAILS
15	NEOPRENE EXPANSION JOINT
16	TEMPORARY CONCRETE BARRIER
17	BAR SPLICER ASSEMBLY DETAILS

GENERAL NOTES

TRAFFIC CONTROL STANDARD 701402 SHALL BE APPLIED AS DIRECTED BY THE ENGINEER. CONCRETE BARRIER IS REQUIRED ANY TIME THE DECK HAS AN OPEN HOLE FOR JOINT REPLACEMENT WORK. FOR OTHER WORK, THE CONCRETE BARRIER IS NOT REQUIRED. BUFFER ZONE AND SIGNS SHALL EQUAL STANDARD 701406 WHILE PERFORMING WORK OUTSIDE THE BARRIER, WITH COST INCLUDED IN TRAFFIC CONTROL AND PROTECTION STANDARD 701402.

STANDARDS

△ 701101
~~701402-03~~
 701406-03 (For Information Only)
 702001-04
 701402-05
 701400-01

DESIGNED	
CHECKED	
DRAWN	RKG
CHECKED	CNT

△ REVISED
4-12-04

Rev.

PREPARED BY:	<i>Joe Idankiewicz</i> DISTRICT STUDIES & PLANS ENGINEER
EXAMINED BY:	<i>James Patrick Emery</i> DISTRICT LAND ACQUISITION ENGINEER
EXAMINED BY:	<i>[Signature]</i> DISTRICT PROGRAM DEVELOPMENT ENGINEER
EXAMINED BY:	<i>[Signature]</i> DISTRICT OPERATIONS ENGINEER
EXAMINED BY:	<i>Joseph Lemire</i> DISTRICT CONSTRUCTION ENGINEER
EXAMINED BY:	<i>Bruce W. Decker</i> DISTRICT MATERIALS ENGINEER
EXAMINED BY:	T-23 DISTRICT PROJECT IMPLEMENTATION ENGINEER
APPROVED BY:	<i>Thomas A. Verma</i> DISTRICT ENGINEER
DATE	February 6, 2004 20