

SP	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0021			
					HSIP FUNDS (90% FEDERAL / 10% LOCAL)		NON HSIP (100% LOCAL)	
					ORCHARD ROAD	FABYAN PARKWAY	ORCHARD ROAD	FABYAN PARKWAY
**	20200100	EARTH EXCAVATION	CU YD	116			34	82
**	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	335			146	189
**	25000210	SEEDING, CLASS 2A	ACRE	1.0			0.5	0.5
**	25100630	EROSION CONTROL BLANKET	SQ YD	335			146	189
**	31101200	SUBBASE GRANULAR MATERIAL, TYPE B, 4"	SQ YD	186			39	147
**	31101600	SUBBASE GRANULAR MATERIAL, TYPE B, 8"	SQ YD	112			41	71
**	40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUNDS	50			25	25
**	40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	12			6	6
**	42001300	PROTECTIVE COAT	SQ YD	246			55	191
**	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	1,665			345	1,320
**	42400800	DETECTABLE WARNINGS	SQ FT	114			53	61
**	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	182			32	150
**	44000600	SIDEWALK REMOVAL	SQ FT	638				638
**	60600605	CONCRETE CURB, TYPE B	FOOT	166			36	130
**	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	96				96
**	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	32			32	
	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	116			34	82
	66900530	SOIL DISPOSAL ANALYSIS	EACH	3			1	2
	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1			0.5	0.5
	66901006	REGULATED SUBSTANCES MONITORING	CAL DAY	7			2	5
	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1			0.5	0.5

**DENOTES SPECIALTY ITEM

MODEL: P:\DWG\18-00493-00-SP\18-00493-00-SP.dwg; FILE NAME: 18-00493-00-SP\18-00493-00-SP.dwg; USER: JSM; DATE: 03/26/2021



USER NAME =	DESIGNED - JSM/AH	REVISED - JSM 03/26/2021
PLOT SCALE =	DRAWN - JSM/AH	REVISED -
PLOT DATE =	CHECKED - JAC/MET	REVISED -
	DATE - 01/13/2021	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

KDOT 2018 HIGHWAY SAFETY IMPROVEMENT PROJECT (HSIP)
SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 4 SHEETS STA. TO STA.

F.A.P. RTE. 363	SECTION 18-00493-00-SP	COUNTY KANE	TOTAL SHEETS 46	SHEET NO. 3
CONTRACT NO. 61G91			ILLINOIS FED. AID PROJECT	