

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY	NONE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	10	10	
20100500	TREE REMOVAL, ACRES	ACRE	0.75	0.75	
20200100	EARTH EXCAVATION	CU YD	6596	6596	
20400800	FURNISHED EXCAVATION	CU YD	23631	23631	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1050	1050	
28000305	TEMPORARY DITCH CHECKS	FOOT	325	325	
28000400	PERIMETER EROSION BARRIER	FOOT	5985	5985	
28000500	INLET AND PIPE PROTECTION	EACH	12	12	
28300400	AGGREGATE DITCH	TON	1245	1245	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	348	348	
35600700	HOT-MIX ASPHALT BASE COURSE WIDENING, 6"	SO YD	3225	3225	
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	1164	1164	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	9371	9371	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	305	305	

• SEE SPECIAL PROVISIONS
 Δ SPECIALTY ITEMS

Δ REVISED 4-6-21



USER NAME =	DESIGNED -	REVISED -
PLOT SCALE =	CHECKED -	REVISED -
PLOT DATE =	DRAWN -	REVISED -
	CHECKED -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
574	19-00056-07-PV	MENARD	63	3
			CONTRACT NO. 93736	
ILLINOIS FED. AID PROJECT				

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY	
				0004	NONE
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2	
54262715	METAL FLARED END SECTIONS 15"	EACH	8	8	
54262718	METAL FLARED END SECTIONS 18"	EACH	4	4	
54262724	METAL FLARED END SECTIONS 24"	EACH	2	2	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	290	290	
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	40	40	
67100100	MOBILIZATION	L SUM	1	1	
70107025	CHANGEABLE MESSAGE SIGN	CAL. DA	150	150	
△ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	15530	15530	
* X0327112	STUMP REMOVAL, ACRES	ACRE	0.75	0.75	
* X0327301	RELOCATE EXISTING MAILBOX	EACH	10	10	
* X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	10.5	10.5	
* X6061460	PAVED DITCH (SPECIAL)	FOOT	22	22	
* X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
# Z0076600	TRAINEES	HOURL	1000		
* Z0023602	GRANULAR CULVERT BACKFILL	CU YD	1824	1824	
# Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURL	1000		
* Z0041500	PLUG EXISTING CULVERTS	EACH	2	2	

• SEE SPECIAL PROVISIONS
 △ SPECIALTY ITEMS
 # = 0042

△ REVISED 4-6-21



USER NAME *	DESIGNED -	REVISED -
PLOT SCALE *	CHECKED -	REVISED -
PLOT DATE *	DRAWN -	REVISED -
	CHECKED -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 3 OF 3 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
574	19-00056-07-PV	MENARD	63	5
CONTRACT NO. 93736			ILLINOIS FED. AID PROJECT	



X0327112 STUMP REMOVAL, ACRES	
LOCATION	TREE REMOVAL (ACRES)
	ACRE
STA. 52+55 TO STA. 54+48 27' LT. TO 53' LT.	0.04
STA. 56+08 TO STA. 62+87 38' LT. TO 66' LT.	0.28
STA. 58+49 TO STA. 62+07 27' RT. TO 43' RT.	0.06
STA. 63+04 TO STA. 66+11 37' RT. TO 51' RT.	0.09
STA. 66+93 TO STA. 69+69 35' RT. TO 44' RT.	0.02
STA. 84+48 TO STA. 84+50 47' RT.	0.01
STA. 87+77 TO STA. 90+52 40' RT. TO 70' RT.	0.08
STA. 91+87 TO STA. 93+30 32' RT. TO 51' RT.	0.03
STA. 97+39 TO STA. 98+06 34' RT. TO 48' RT.	0.02
STA. 98+35 TO STA. 100+70 30' RT. TO 43' RT.	0.03
TOTAL	0.66

SAY 0.75 ACRE

28000305 TEMPORARY DITCH CHECKS	
LOCATION	TEMPORARY DITCH CHECKS
	FOOT
STA. 53+00 76' LT. & 47' RT.	16
STA. 54+00 39' LT. & 48' RT.	16
STA. 57+00 29' LT. & 30' RT.	18
STA. 58+00 38' LT. & 37' RT.	18
STA. 59+00 69' LT. & 77' RT.	17
STA. 60+50 100' LT. & 85' RT.	16
STA. 61+50 81' LT. & 85' RT.	16
STA. 62+50 45' LT. & 63' RT.	16
STA. 64+00 29' LT. & 31' RT.	16
STA. 66+00 29' LT. & 31' RT.	16
STA. 68+50 57' LT. & 47' RT.	16
STA. 69+50 62' LT. & 61' RT.	16
STA. 70+50 40' LT.	8
STA. 71+50 36' LT.	8
STA. 74+00 29' LT.	8
STA. 78+50 58' LT. & 45' RT.	16
STA. 79+50 54' LT. & 45' RT.	16
STA. 82+00 37' LT. & 34' RT.	16
STA. 85+00 39' LT. & 33' RT.	16
STA. 88+00 42' LT. & 36' RT.	16
STA. 94+00 37' LT.	8
STA. 99+00 35' LT. & 33' RT.	16
TOTAL	325

EARTHWORK				
LOCATION	20200100 EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
STA. 50+00 TO STA. 63+00	2209	1657	17126	-15469
STA. 63+00 TO STA. 77+50	988	741	4908	-4167
STA. 77+50 TO STA. 92+00	2813	2110	4575	-2465
STA. 92+00 TO STA. 105+30	586	439	1969	-1530
TOTAL	6596	4947	28578	-23631

28000250 TEMPORARY EROSION CONTROL SEEDING	
LOCATION	TEMPORARY EROSION CONTROL SEEDING
	POUND
STA. 50+00 TO STA. 63+00	340
STA. 63+25 TO STA. 77+50	250
STA. 77+50 TO STA. 92+00	300
STA. 92+00 TO STA. 105+30	160
TOTAL	1050

28300400 AGGREGATE DITCH	
LOCATION	AGGREGATE DITCH
	TON
STA. 52+36 TO STA. 54+00 RT.	78
STA. 52+68 TO STA. 54+50 LT.	84
STA. 56+50 TO STA. 59+00 LT.	126
STA. 56+65 TO STA. 64+00 RT.	357
STA. 60+50 TO STA. 63+00 LT.	115
STA. 67+50 TO STA. 70+50 LT.	136
STA. 68+00 TO STA. 69+50 RT.	70
STA. 76+50 TO STA. 79+50 LT.	128
STA. 76+50 TO STA. 79+50 RT.	151
TOTAL	1245

28000400 PERIMETER EROSION BARRIER	
LOCATION	PERIMETER EROSION BARRIER
	FOOT
STA. 50+00 TO STA. 54+50 LT.	466
STA. 50+00 TO STA. 54+50 RT.	453
STA. 56+70 TO STA. 74+00 RT.	1790
STA. 58+00 TO STA. 74+30 LT.	1625
STA. 77+00 TO STA. 84+50 RT.	750
STA. 78+50 TO STA. 82+50 LT.	401
STA. 100+00 TO STA. 105+00 LT.	500
TOTAL	5985

35100100 AGGREGATE BASE COURSE, TYPE A	
LOCATION	AGGREGATE BASE COURSE, TYPE A
	TON
STA. 53+07 TO STA. 53+62	101
STA. 60+35 TO STA. 61+05	129
STA. 68+90 TO STA. 69+18	52
STA. 78+91 TO STA. 79+17	48
SHORT STREET	18
TOTAL	348

28000500 INLET & PIPE PROTECTION	
LOCATION	INLET & PIPE PROTECTION
	EACH
STA. 51+80 42.5' RT.	1
STA. 53+72 60' RT.	1
STA. 58+10 38.5' RT.	1
STA. 61+05 105' RT.	1
STA. 63+80 29.5' LT.	1
STA. 69+04 60' RT.	1
STA. 71+29 36' LT.	1
STA. 74+27 31' LT.	1
STA. 79+04 74' RT.	1
STA. 85+03 45' RT.	1
STA. 87+77 42' LT.	1
STA. 100+96 32' RT.	1
TOTAL	12

35600700 HOT-MIX ASPHALT BASE COURSE WIDENING	
LOCATION	HOT-MIX ASPHALT BASE COURSE WIDENING, 6"
	SO. YD.
STA. 50+00 TO STA. 58+00	439
STA. 58+00 TO STA. 59+50	125
STA. 59+50 TO STA. 60+35	95
STA. 61+05 TO STA. 61+50	50
STA. 61+50 TO STA. 63+00	125
STA. 63+00 TO STA. 67+50	250
STA. 67+50 TO STA. 68+00	34
STA. 68+00 TO STA. 70+00	156
STA. 70+00 TO STA. 70+50	34
STA. 70+50 TO STA. 105+30	1917
TOTAL	3225

REVISED 4-6-21



USER NAME =	DESIGNED -	REVISED -
PLOT SCALE =	CHECKED -	REVISED -
PLOT DATE =	DRAWN -	REVISED -
	CHECKED -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

QUANTITY SCHEDULES		
SCALE: NONE	SHEET NO. 1 OF 4 SHEETS	STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
574	19-00056-07-PV	MENARD	63	15
CONTRACT NO. 93736				
ILLINOIS FED. AID PROJECT				