

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
D1 OVD SIN STR REP & REPL09-22
Various Counties
Sheet 4 of 33
Contract Number 46033

District 1
Schedule of Overhead Sign Structure Repair & Replacement

Location No.:	1-01	State I.D. No.:	1S016I094L033.0-000 (RS-9) N1				
County:	Cook	Route:	I - 94	M.P.:	33	Direction:	NB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE III-A	FOOT	95.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	546.00					
REMOVE & REINSTALL WALKWAY	FOOT	77.67					
REPLACE / TIGHTEN CLIP PER SIGN	EACH	3.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
This structure is being downsized from a Type IV to a Type III.							
End Support will be nonstandard designs to match existing anchor bolt patterns of existing concrete foundations.							
Field measurements are required before ordering materials.							
This work shall be completed during District 1 night-time hours.							

Location No.:	1-02	State I.D. No.:	1S016I094L030.8-000 (RS-10) P1				
County:	Cook	Route:	I - 94	M.P.:	30.8	Direction:	NB
Description of Work	Unit	Quantity					
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00					
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00					
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	77.00					
REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE SIGN PANEL - TYPE 3	SQ FT	301.00					
SIGN PANEL - TYPE 3	SQ FT	385.00					
REPLACE HANDRAIL SUPPORT	EACH	1.00					
End Support will be nonstandard designs to match existing anchor bolt patterns of existing concrete foundations.							
Field measurements are required before ordering materials.							
This work shall be completed during District 1 night-time hours.							

Location No.:	1-03	State I.D. No.:	1S016I094L036.0-000 (RS-7) J1				
County:	Cook	Route:	I - 94	M.P.:	36	Direction:	NB
Description of Work	Unit	Quantity					
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00					
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00					
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	82.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
TIGHTEN U-BOLT	EACH	2.00					
FURNISH & INSTALL INTERNAL TRUSS CLAMP	EACH	1.00					
End Support will be nonstandard designs to match existing anchor bolt patterns of existing concrete foundations.							
Field measurements are required before ordering materials.							
This work shall be completed during District 1 night-time hours.							

Location No.:	1-04	State I.D. No.:	1S022I290L006.8 (ST-48) G2				
County:	DuPage	Route:	I - 290	M.P.:	6.8	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	1.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE	EACH	1.00					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	2.00					
REPLACE SPLICE FLANGE BOLT	EACH	40.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-05	State I.D. No.:	1S022S083R000.0-002 (BTN-3) D7				
County:	DuPage	Route:	IL 83	M.P.:	0	Direction:	NB
Description of Work	Unit	Quantity					
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00					
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	87.00					
REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-06	State I.D. No.:	1S022S083R000.0-001 (BTN-2) D5				
County:	DuPage	Route:	IL 83	M.P.:	0	Direction:	NB
Description of Work	Unit	Quantity					
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00					
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	84.00					
REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-07	State I.D. No.:	1C016I290L019.8 (CLW-4) O1				
County:	Cook	Route:	I - 290	M.P.:	19.8	Direction:	WB
Description of Work	Unit	Quantity					
REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE	EACH	1.00					

Location No.:	1-08	State I.D. No.:	1S049U041R000.0				
County:	LAKE	Route:	US 41	M.P.:	0	Direction:	NB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE I-A	FOOT	64.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
REMOVE & REINSTALL WALKWAY	FOOT	38.00					
REMOVE SIGN PANEL - TYPE 3	SQ FT	263.00					
SIGN PANEL - TYPE 3	SQ FT	197.50					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	6.00					