



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 9, 2009

SUBJECT: FAP Route 344
Project F-0344 (049)
Section (46-15 & 47) WRS-3
Lake County
Contract No. 60957
Item No. 180, April 24, 2009 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the entire Schedule of Prices.
2. Revised sheets 1, 12, 13, 14 & 90 - 93 of the Plans.
3. Added sheets 93A - 93D to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles J. Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Bill Frey; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2000320	T-ACER MIY MOR 2-1/2	EACH	5.000				
A2002470	T-BETUL NG HRT CL 8'	EACH	7.000				
A2002820	T-CATALPA SPEC 2-1/2	EACH	9.000				
A2002920	T-CELTIS OCCID 2-1/2	EACH	3.000				
A2004720	T-GLED TRI-I SM 2-1/2	EACH	11.000				
A2006522	T-ULMUS PARV ALLE 2.5	EACH	4.000				
A2006716	T-QUERCUS MACR 2	EACH	8.000				
A2007920	T-TILIA AMER RD 2-1/2	EACH	21.000				
A2018720	T-ULMUS CARP MO 2-1/2	EACH	13.000				
B2006270	T-SYRING RET CL 8'	EACH	10.000				
C2C058G3	S-RHUS AROMA GL CG 3G	EACH	51.000				
C2C062G5	S-RHUS TYPH TE CG 5G	EACH	15.000				
C2002636	S-EUONY ALAT COMP 3'	EACH	90.000				
C2011936	S-VIBURN DEN R S 3'	EACH	56.000				
K0030401	P P CAL ACUT K F 1GAL	EACH	159.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
K0030404	PER RUD FULG GLDST 1G	EACH	114.000				
K0030411	P ECH PURP MAG CON 1G	EACH	209.000				
K0039126	HEMERCL HAP RET 1G	EACH	176.000				
XX003660	FOCC62.5/125 MM24SM12	FOOT	6,590.000				
XX005656	INLET FILTER CLEANING	EACH	600.000				
XX006610	GRASSES SCHIZ SCOP 1G	EACH	210.000				
XZ030256	IMP ATTN RELO NRN TL3	EACH	4.000				
XZ030258	IMP ATTN REPL NRN TL3	EACH	2.000				
XZ030260	IMP ATTN TEMP NRN TL3	EACH	6.000				
X0322256	TEMP INFO SIGNING	SQ FT	51.000				
X0322852	ASTER NOVAE ANG PD 1G	EACH	127.000				
X0322925	ELCBL C TRACER 14 1C	FOOT	6,590.000				
X0323670	PREFORM DETECT LOOP	FOOT	1,768.000				
X0325775	WET RF TEM TAPE T3 4	FOOT	45,708.000				
X0325837	WET RF TEM TAPE T3 6	FOOT	1,141.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0325840	WET RF TEM TAPE T3 12	FOOT	527.000				
X0325841	WET RF TEM TAPE T3 24	FOOT	533.000				
X0325842	WET RF TEM TAPE T3 LS	SQ FT	582.000				
X0325890	RE-OPTIMIZE SIG SYS 1	EACH	1.000				
X0326289	MAN SPL 7 DIA T1F CL	EACH	9.000				
X0326290	S MAA & P DMA 16 & 38	EACH	1.000				
X0326291	S MAA & P DMA 16 & 42	EACH	2.000				
X0326292	S MAA & P DMA 14 & 46	EACH	1.000				
X0326293	S MAA & P DMA 20 & 26	EACH	1.000				
X0712400	TEMP PAVEMENT	SQ YD	10,285.000				
X4067107	POL LB MM IL4.75 N50	TON	509.000				
X4403300	CONC MEDIAN REMOV	SQ FT	3,725.000				
X8050010	SERV INSTALL GRND MT	EACH	1.000				
X8050015	SERV INSTALL POLE MT	EACH	1.000				
X8620020	UNINTER POWER SUPPLY	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X8730027	ELCBL C GROUND 6 1C	FOOT	2,129.000				
X8730275	ELCBL C SIGNAL 20 3C	FOOT	744.000				
Z0001050	AGG SUBGRADE 12	SQ YD	63,979.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0018400	DRAINAGE STR ADJ	EACH	42.000				
Z0018500	DRAINAGE STR CLEANED	EACH	11.000				
Z0018900	DRILL-GROUT DOW BARS	EACH	743.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0076600	TRAINEES	HOUR	2,000.000		0.800		1,600.000
20100110	TREE REMOV 6-15	UNIT	430.000				
20100210	TREE REMOV OVER 15	UNIT	299.000				
20101000	TEMPORARY FENCE	FOOT	1,164.000				
20101100	TREE TRUNK PROTECTION	EACH	32.000				
20200100	EARTH EXCAVATION	CU YD	35,586.000				
20201200	REM & DISP UNS MATL	CU YD	672.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20700420	POROUS GRAN EMB SUBGR	CU YD	2,663.000				
20800150	TRENCH BACKFILL	CU YD	1,321.000				
21001000	GEOTECH FAB F/GR STAB	SQ YD	7,358.000				
21101505	TOPSOIL EXC & PLAC	CU YD	6,925.000				
21101685	TOPSOIL F & P 24	SQ YD	3,298.000				
21101815	COMPOST F & P 4	SQ YD	9,680.000				
21301048	EXPLOR TRENCH 48	FOOT	1,000.000				
25000210	SEEDING CL 2A	ACRE	10.000				
25000312	SEEDING CL 4A	ACRE	2.000				
25000400	NITROGEN FERT NUTR	POUND	947.000				
25000500	PHOSPHORUS FERT NUTR	POUND	947.000				
25000600	POTASSIUM FERT NUTR	POUND	947.000				
25000775	SELECT MOWING STAKES	EACH	74.000				
25100630	EROSION CONTR BLANKET	SQ YD	58,080.000				
25200110	SODDING SALT TOLERANT	SQ YD	3,797.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25200200	SUPPLE WATERING	UNIT	518.000				
28000250	TEMP EROS CONTR SEED	POUND	20,000.000				
28000300	TEMP DITCH CHECKS	EACH	67.000				
28000310	AGG DITCH CHECKS	EACH	67.000				
28000400	PERIMETER EROS BAR	FOOT	5,148.000				
28000510	INLET FILTERS	EACH	119.000				
28100107	STONE RIPRAP CL A4	SQ YD	89.000				
28200200	FILTER FABRIC	SQ YD	89.000				
35501308	HMA BASE CSE 6	SQ YD	864.000				
35501316	HMA BASE CSE 8	SQ YD	259.000				
35501324	HMA BASE CSE 10	SQ YD	3,500.000				
35600700	HMA BC WID 6	SQ YD	356.000				
40201000	AGGREGATE-TEMP ACCESS	TON	350.000				
40600100	BIT MATLS PR CT	GALLON	4,605.000				
40600300	AGG PR CT	TON	93.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600895	CONSTRUC TEST STRIP	EACH	2.000				
40600982	HMA SURF REM BUTT JT	SQ YD	412.000				
40600990	TEMPORARY RAMP	SQ YD	204.000				
40603085	HMA BC IL-19.0 N70	TON	486.000				
40603240	P HMA BC IL19.0 N90	TON	449.000				
40603310	HMA SC "C" N50	TON	137.000				
40603340	HMA SC "D" N70	TON	527.000				
40603595	P HMA SC "F" N90	TON	1,284.000				
42000411	PCC PVT 9 1/2 JOINTD	SQ YD	45,282.000				
42001300	PROTECTIVE COAT	SQ YD	55,208.000				
44000100	PAVEMENT REM	SQ YD	46,107.000				
44000155	HMA SURF REM 1 1/2	SQ YD	1,196.000				
44000159	HMA SURF REM 2 1/2	SQ YD	12,933.000				
44000200	DRIVE PAVEMENT REM	SQ YD	1,751.000				
44000500	COMB CURB GUTTER REM	FOOT	3,952.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44002218	HMA RM OV PATCH 4 1/2	SQ YD	2,826.000				
44002500	GUT OUTLET REM	EACH	2.000				
44004250	PAVED SHLD REMOVAL	SQ YD	1,725.000				
44201741	CL D PATCH T2 8	SQ YD	3,975.000				
44201761	CL D PATCH T1 10	SQ YD	590.000				
44201765	CL D PATCH T2 10	SQ YD	840.000				
44201769	CL D PATCH T3 10	SQ YD	965.000				
44201771	CL D PATCH T4 10	SQ YD	740.000				
44300200	STRIP REF CR CON TR	FOOT	1,629.000				
48100500	AGGREGATE SHLDS A 6	SQ YD	789.000				
48203021	HMA SHOULDERS 6	SQ YD	300.000				
48203029	HMA SHOULDERS 8	SQ YD	120.000				
50104400	CONC HDWL REM	EACH	7.000				
50105220	PIPE CULVERT REMOV	FOOT	822.000				
54010202	PCBC 2X2	FOOT	35.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
542A0220	P CUL CL A 1 15	FOOT	197.000				
54213657	PRC FLAR END SEC 12	EACH	8.000				
54213660	PRC FLAR END SEC 15	EACH	12.000				
54213663	PRC FLAR END SEC 18	EACH	2.000				
54213669	PRC FLAR END SEC 24	EACH	1.000				
54213681	PRC FLAR END SEC 36	EACH	3.000				
54214719	PRCF END S EL EQRS 24	EACH	1.000				
54247090	GRATING-C FL END S 12	EACH	8.000				
54247100	GRATING-C FL END S 15	EACH	12.000				
54247110	GRATING-C FL END S 18	EACH	2.000				
54247130	GRATING-C FL END S 24	EACH	1.000				
54247170	GRATING-C FL END S 36	EACH	3.000				
54248130	GRT-C FL END S EQV 24	EACH	1.000				
55019500	SS 1 RCP CL 4 12	FOOT	151.000				
55019900	SS 1 RCP CL 4 24	FOOT	199.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
55020300	SS 1 RCP CL 3 36	FOOT	302.000				
55021600	SS 2 RCP CL 3 12	FOOT	3,631.000				
55021700	SS 2 RCP CL 3 15	FOOT	572.000				
55021800	SS 2 RCP CL 3 18	FOOT	34.000				
55022000	SS 2 RCP CL 3 24	FOOT	663.000				
55022400	SS 2 RCP CL 3 36	FOOT	228.000				
55022600	SS 2 RCP CL 3 48	FOOT	879.000				
55022700	SS 2 RCP CL 3 54	FOOT	584.000				
55022800	SS 2 RCP CL 2 60	FOOT	303.000				
55024900	SS 3 RCP CL 4 60	FOOT	194.000				
55034300	SS 1 RCEP S30 R19	FOOT	80.000				
55034700	SS 1 RCEP S53 R34	FOOT	179.000				
55034900	SS 1 RCEP S68 R43	FOOT	386.000				
55035800	SS 2 RCEP S53 R34	FOOT	547.000				
55039700	SS CLEANED	FOOT	500.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
55100500	STORM SEWER REM 12	FOOT	80.000				
55101200	STORM SEWER REM 24	FOOT	210.000				
60100060	CONC HDWL FOR P DRAIN	EACH	4.000				
60107600	PIPE UNDERDRAINS 4	FOOT	3,102.000				
60200105	CB TA 4 DIA T1F OL	EACH	3.000				
60200205	CB TA 4 DIA T1F CL	EACH	2.000				
60200805	CB TA 4 DIA T8G	EACH	10.000				
60201340	CB TA 4 DIA T24F&G	EACH	48.000				
60203905	CB TA 5 DIA T1F CL	EACH	1.000				
60218400	MAN TA 4 DIA T1F CL	EACH	6.000				
60221100	MAN TA 5 DIA T1F CL	EACH	7.000				
60223800	MAN TA 6 DIA T1F CL	EACH	16.000				
60224446	MAN TA 7 DIA T1F CL	EACH	5.000				
60231700	MAN SPL 5 DIA T1F CL	EACH	4.000				
60232900	MAN SPL 6 DIA T1F CL	EACH	13.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60240301	INLETS TB T8G	EACH	2.000				
60240328	INLETS TB T24F&G	EACH	54.000				
60252800	CB RECONST	EACH	5.000				
60257900	MAN RECONST	EACH	5.000				
60500040	REMOV MANHOLES	EACH	1.000				
60500050	REMOV CATCH BAS	EACH	4.000				
60500060	REMOV INLETS	EACH	1.000				
60600095	CLASS SI CONC OUTLET	CU YD	8.000				
60603800	COMB CC&G TB6.12	FOOT	1,454.000				
60605000	COMB CC&G TB6.24	FOOT	15,927.000				
60611600	COMB CC&G SPL	FOOT	12,385.000				
60618300	CONC MEDIAN SURF 4	SQ FT	3,788.000				
60619600	CONC MED TSB6.12	SQ FT	5,747.000				
60624600	CORRUGATED MED	SQ FT	228.000				
63000000	SPBGR TY A	FOOT	338.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63100045	TRAF BAR TERM T2	EACH	2.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	2.000				
63200310	GUARDRAIL REMOV	FOOT	560.000				
67000400	ENGR FIELD OFFICE A	CAL MO	24.000				
67100100	MOBILIZATION	L SUM	1.000				
70101800	TRAF CONT & PROT SPL	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	360.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	24.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	218.000				
70300220	TEMP PVT MK LINE 4	FOOT	65,964.000				
70300240	TEMP PVT MK LINE 6	FOOT	570.000				
70300260	TEMP PVT MK LINE 12	FOOT	710.000				
70300280	TEMP PVT MK LINE 24	FOOT	204.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	23,997.000				
70400100	TEMP CONC BARRIER	FOOT	1,391.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70400200	REL TEMP CONC BARRIER	FOOT	693.000				
72000100	SIGN PANEL T1	SQ FT	153.000				
72000200	SIGN PANEL T2	SQ FT	28.000				
72400310	REMOV SIGN PANEL T1	SQ FT	399.000				
72400710	RELOC SIGN PANEL T1	SQ FT	399.000				
72900100	METAL POST TY A	FOOT	400.000				
72900200	METAL POST TY B	FOOT	80.000				
78000100	THPL PVT MK LTR & SYM	SQ FT	188.000				
78000200	THPL PVT MK LINE 4	FOOT	5,411.000				
78000300	THPL PVT MK LINE 5	FOOT	2,650.000				
78000400	THPL PVT MK LINE 6	FOOT	509.000				
78000600	THPL PVT MK LINE 12	FOOT	367.000				
78000650	THPL PVT MK LINE 24	FOOT	101.000				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	250.000				
78008210	POLYUREA PM T1 LN 4	FOOT	4,258.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78008220	POLYUREA PM T1 LN 5	FOOT	116.000				
78008230	POLYUREA PM T1 LN 6	FOOT	1,160.000				
78008270	POLYUREA PM T1 LN 24	FOOT	378.000				
78100100	RAISED REFL PAVT MKR	EACH	614.000				
78300100	PAVT MARKING REMOVAL	SQ FT	8,170.000				
81000600	CON T 2 GALVS	FOOT	7,414.000				
81000700	CON T 2 1/2 GALVS	FOOT	115.000				
81001000	CON T 4 GALVS	FOOT	134.000				
81018500	CON P 2 GALVS	FOOT	294.000				
81018900	CON P 4 GALVS	FOOT	512.000				
81400100	HANDHOLE	EACH	24.000				
81400200	HD HANDHOLE	EACH	3.000				
81400300	DBL HANDHOLE	EACH	2.000				
81900200	TR & BKFIL F ELECT WK	FOOT	7,663.000				
85700200	FAC T4 CAB	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60957

State Job # - C-91-209-00
 PPS NBR - 1-71097-1400
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - (46-1S&47)WRS-3

Project Number
 F-0344/049/

Route
 FAP 344

* REVISED : APRIL 8, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
86400100	TRANSCEIVER - FIB OPT	EACH	2.000				
87301225	ELCBL C SIGNAL 14 3C	FOOT	744.000				
87301245	ELCBL C SIGNAL 14 5C	FOOT	1,734.000				
87301255	ELCBL C SIGNAL 14 7C	FOOT	3,344.000				
87301305	ELCBL C LEAD 14 1PR	FOOT	4,460.000				
87301805	ELCBL C SERV 6 2C	FOOT	95.000				
87702190	S MAA & P DMA 16 & 28	EACH	1.000				
87702360	S MAA & P DMA 26 & 40	EACH	1.000				
87702550	S MAA & P DMA 34 & 40	EACH	1.000				
87800150	CONC FDN TY C	FOOT	8.000				
87800415	CONC FDN TY E 36D	FOOT	120.000				
87900200	DRILL EX HANDHOLE	EACH	1.000				
88030020	SH LED 1F 3S MAM	EACH	8.000				
88030080	SH LED 1F 4S MAM	EACH	4.000				
88030110	SH LED 1F 5S MAM	EACH	12.000				

