

CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	URBAN TOTAL QUANTITY	CONSTRUCTION CODE				
				1000-2A ROADWAY	TRAFFIC SIGNALS - CASEY RD	TRAFFIC SIGNALS - ARBOR BLVD	TRAFFIC SIGNAL INTERCONNECT	1000-2A ROADWAY
				80% FED 20% STATE				100% STATE
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1				
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	3	3				
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	EACH	1	1				
54247100	GRATING FOR CONCRETE FLARED END SECTION 15"	EACH	12	12				
54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	2	2				
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1				
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	3	3				
54248130	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 24"	EACH	1	1				
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	151	151				
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	199	199				
55020300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	302	302				
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	3,631	3,631				
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	572	572				
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	34	34				
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	663	663				
55022400	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	228	228				
55022600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 48"	FOOT	879	879				
55022700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 54"	FOOT	584	584				
55022800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS II 60"	FOOT	303	303				
55024900	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 60"	FOOT	194	194				
55034300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19	FOOT	80	80				

* INDICATES SPECIALTY ITEM

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - MAP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = #SCALE#	DRAWN - JRH	REVISED -		SCALE: NONE	SHEET NO. 4 OF 11 SHEETS	STA.	TO STA.	344	(46-1S&47)WRS-3	LAKE	176	7
	PLOT DATE = #DATE#	CHECKED - JW	REVISED -		U.S. ROUTE 45 RECONSTRUCTION		CONTRACT NO.		FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				
		DATE - 01-03-08	REVISED -										