

CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	URBAN TOTAL QUANTITY	CONSTRUCTION CODE				
				J000-2A ROADWAY	Y031-IF TRAFFIC SIGNALS - CASEY RD 51. LIBERTYVILLE	Y031-IF TRAFFIC SIGNALS - ARBOR BLVD 51. WARREN TWP.	Y031-IF TRAFFIC SIGNAL INTERCONNECT	I000-2A ROADWAY
				80% FED 20% STATE	80% FED 10% STATE 5% LAKE CTY	80% FED 10% STATE 5% GRAYSLAKE	80% FED 20% STATE	100% STATE
78300100	PAVEMENT MARKING REMOVAL	SQ FT	8,170	8,170				
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	7,414		524	505	6,385	
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	115		55	60		
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	134		60	74		
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	294		107	55	132	
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	512		257	255		
* 81400100	HANDHOLE	EACH	24		7	8	9	
* 81400200	HEAVY-DUTY HANDHOLE	EACH	3		2	1		
* 81400300	DOUBLE HANDHOLE	EACH	2		1	1		
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	7,663		639	639	6,385	
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2		1	1		
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	2		1	1		
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C **	FOOT	744		304	440		
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,734		874	860		
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3,344		1,646	1,698		
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4,460		1,948	2,512		
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	95		86	9		
* X0326291	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 16 ^{FT.} AND 42 ^{FT.}	EACH	2		2	0		
* X0326290	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 16 ^{FT.} AND 38 ^{FT.}	EACH	1		1	0		
* X0326292	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 14 ^{FT.} AND 46 ^{FT.}	EACH	1		1	0		
* 877002190	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 16 ^{FT.} AND 28 ^{FT.}	EACH	1		0	1		
* X0326293	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 20 ^{FT.} AND 26 ^{FT.}	EACH	1		0	1		
* 87702360	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 26 ^{FT.} AND 40 ^{FT.}	EACH	1		0	1		
* 87702550	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 34 ^{FT.} AND 40 ^{FT.}	EACH	1		0	1		

** PAID FOR 100% BY GRAYSLAKE FIRE PROTECTION DISTRICT Y031-37

* INDICATES SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED - MAP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#		DRAWN - JRH	REVISED -					344	(46-1S&47)WRS-3	LAKE	176	11
	PLOT SCALE = #SCALE#	CHECKED - JW	REVISED -		SCALE: NONE			SHEET NO. 8 OF 11 SHEETS STA. TO STA.			U.S. ROUTE 45 RECONSTRUCTION CONTRACT NO.	
	PLOT DATE = #DATE#	DATE - 01-03-08	REVISED -		FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT							