

CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	URBAN TOTAL QUANTITY	CONSTRUCTION CODE				
				1000-2A ROADWAY	Y031-1P TRAFFIC SIGNALS - CASEY RD 51. LIBERTYVILLE	Y031-1P TRAFFIC SIGNALS - ARBOR BLVD 51. WARREN TWP.	Y031-1P TRAFFIC SIGNAL INTERCONNECT	1000-2A ROADWAY
				80% FED 20% STATE	80% FED 10% STATE 5% LAKE CTY	80% FED 10% STATE 5% GRAYSLAKE	80% FED 20% STATE	100% STATE
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8		4	4		
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	120		60	60		
* 87900200	DRILL EXISTING HANDHOLE	EACH	1				1	
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8		4	4		
* 88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST-ARM MOUNTED	EACH	4		0	4		
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	12		8	4		
* 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	24		12	12		
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	20		10	10		
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	68		0	68		
* 88700200	LIGHT DETECTOR **	EACH	5		2	3		
* 88700300	LIGHT DETECTOR AMPLIFIER **	EACH	2		1	1		
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1		
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1		
* 89502380	REMOVE EXISTING HANDHOLE	EACH	2			2		
* A2000320	TREE, ACER MIYABEI MORTON (STATE STREET MIYABE MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	10	10				
* A2002816	TREE, CATALPA SPECIOSA (NORTHERN CATALPA), 2" CALIPER, BALLED AND BURLAPPED	EACH	9	9				
* A2004720	TREE, GLEDITSIA TRIACANTHOS INERMIS SHADEMASTER (SHADEMASTER THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	17	17				
* A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	9	9				
* A2005556	TREE, NYSSA SYLVATICA (BLACK TUPELO), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	11	11				
* A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	19	19				
* A2007616	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2" CALIPER, BALLED AND BURLAPPED	EACH	20	20				
* A2018720	TREE, ULMUS CARPINIFOLIA MORTON, (ACCOLADE ELM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	21	21				

\*\* PAID FOR 100% BY GRAYSLAKE FIRE PROTECTION DISTRICT - Y031-1D

FILE NAME =	USER NAME = #USER#	DESIGNED - MAP	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#		DRAWN - JRH	REVISED -			344	(46-1S&47)WRS-3	LAKE	176	12	
	PLOT SCALE = #SCALE#	CHECKED - JW	REVISED -			U.S. ROUTE 45 RECONSTRUCTION CONTRACT NO.					
	PLOT DATE = #DATE#	DATE - 01-03-08	REVISED -			FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					
					SCALE: NONE	SHEET NO. 9 OF 11 SHEETS		STA.	TO STA.		