



SECTION A-A
(STA. 249+00 TO STA. 255+00)
(N.T.S.)

PRESTAGE CONSTRUCTION NOTES

WORK SHALL NOT PROCEED ON BOTH SIDES OF TRAFFIC SIMULTANEOUSLY. WHEN PLANS CALL FOR WORK ON BOTH SIDES OF TRAFFIC, WORK ON ONE SIDE SHALL BE COMPLETED AND PROPERLY CLOSED BEFORE BEGINNING WORK ON THE OTHER SIDE.

AS TEMPORARY PAVEMENT WORK PROCEEDS, TRAFFIC CONTROL PER IDOT STD. 701326 SHALL BE INSTALLED. AFTER TEMPORARY WIDENING IS COMPLETED, CLOSE TEMPORARY PAVEMENT UNTIL STAGE 1 TRAFFIC CONTROL IS APPLIED, USING 100' C-C SPACING AND CHECK BARRICADES AT 500' SPACING. AT INTERSECTIONS, PLACE CLOSURE BARRICADES PER IDOT STD. 701701.

FILE NAME =	USER NAME = #USER#	DESIGNED = MAP	REVISED =	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MAINTENANCE OF TRAFFIC - PRE-STAGE CONSTRUCTION	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN = JRH	REVISED =			344	(46-1S&47)WRS-3	LAKE	176	29	
		CHECKED = JW	REVISED =			U.S. ROUTE 45 RECONSTRUCTION		CONTRACT NO. 60957			
		DATE = 12-12-08	REVISED =			SCALE: 1"=50'	SHEET NO. 1 OF 4 SHEETS	STA. 250+00 TO STA. 263+00	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		