

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITY	CONSTRUCTION CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000-2A	BRIDGE X081-2A
28000510	INLET FILTERS	EACH	25	25	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	20	20	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	35	35	
40600300	AGGREGATE (PRIME COAT)	TON	1	1	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	20	20	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	60	60	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	30	30	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	180	180	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	340	340	
44000600	SIDEWALK REMOVAL	SQ FT	180	180	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	9,611		9,611
50102400	CONCRETE REMOVAL	CU YD	167.7		167.7
50157300	PROTECTIVE SHIELD	SQ YD	5,001		5,001
50300255	CONCRETE SUPERSTRUCTURE	CU YD	180.3		180.3
50300260	BRIDGE DECK GROOVING	SQ YD	8,930		8,930
50300300	PROTECTIVE COAT	SQ YD	10,543		10,543
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5,870		5,870
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	5		5
50501110	STRUCTURAL STEEL REMOVAL	POUND	4,050		4,050
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	31,290		31,290
50800515	BAR SPLICERS	EACH	158		158
51500100	NAME PLATES	EACH	1		1
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	5		5
52100530	ANCHOR BOLTS, 1 1/4"	EACH	20		20
58700300	CONCRETE SEALER	SQ FT	694		694
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	550	550	
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	1	1	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	466	466	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	2	4
67100100	MOBILIZATION	L SUM	1	0.2	0.8
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	0.2	0.8
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6,650	6,650	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,100	2,100	

* DENOTES SPECIALTY ITEM
 @ Y080

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITY	CONSTRUCTION CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000-2A	BRIDGE X081-2A
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2,050	2,050	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10,200	10,200	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	525	525	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	330	330	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	90	90	
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	7,200	7,200	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20	20	
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	85	85	
78100300	REPLACEMENT REFLECTOR	EACH	175	175	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	25	25	
78200530	BARRIER WALL MARKERS, TYPE C	EACH	170	170	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	6,700	6,700	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	80	80	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
89502200	MODIFY EXISTING CONTROLLER	EACH	1	1	
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	175	175	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	9,491		9,491
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	50	50	
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	478		478
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	4,182		4,182
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	18,800	18,800	
X0325837	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	250	250	
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	160	160	
X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	73	73	
Z0006201	BRIDGE DECK HYDRO-SCARIFICATION 1"	SQ YD	9,611		9,611
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.2	0.8
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	3,110		3,110
Z0018800	DRAINAGE SYSTEM	L SUM	1		1
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
Z0034390	MODULAR EXPANSION JOINT 6"	FOOT	205		205
Z0034393	MODULAR EXPANSION JOINT 9"	FOOT	68		68
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

@ 20076400 TRAINEES HOUR 1000 1000
 X0321781 MECHANICAL SPLICE EACH 256 256

FILE NAME = N:\PROJECTS\3329_38\Design\ProposedPlan\3329_38-03-ecodgn



Ciorba Group, Inc.
 CONSULTING ENGINEERS
 5507 North Cumberland Avenue, Suite 402
 Chicago, Illinois 60655
 Tel. 773.775.4009 Fax 773.775.4014

USER NAME = mready	DESIGNED - JCC	REVISED -
PLOT SCALE = 1:8000' / 1"	DRAWN - JCC	REVISED -
PLOT DATE = 2/4/2009	CHECKED - MJL	REVISED -
	DATE - 02/25/08	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

FAU 2697 / WILLOW SPRINGS ROAD
 OVER DESPLAINES STREET
 SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. 2697	SECTION 142 B-1-I	COUNTY COOK	TOTAL SHEETS 48	SHEET NO. 3
CONTRACT NO. 60D89				
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				

Rev. 4-9-09