

SUMMARY OF QUANTITIES													
CODE NO	ITEM	UNIT	TOTAL QUANTITY	URBAN 100% FED. J000-2A	ROADWAY & DRAINAGE	TRAFFIC SIGNALS IL 59 @ U.S. ROUTE 30	TRAFFIC SIGNALS IL 59 @ LOCKPORT	ROADWAY LIGHTING	TRAFFIC SIGNALS INTERCONNECT	TRAFFIC SIGNALS TEMPORARY INTERCONNECT	TRAFFIC SIGNALS EVP EQUIPMENT	WATER MAIN/SANITARY SEWER	SIDEWALK
40600300	AGGREGATE (PRIME COAT)	TON	3		3								
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	88		88								
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	77		77								
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	22,138		22,138								
42001300	PROTECTIVE COAT	SQ YD	8,678		8,678								
42001600	PORTLAND CEMENT CONCRETE PAVEMENT (VARIABLE DEPTH)	SQ YD	40									40	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	112		112								
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	179		179								
42300800	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH, SPECIAL	SQ YD	120									120	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	38,440		38,440								
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	9,473		9,473								
42400610	TEMPORARY SIDEWALK	SQ FT	34,641		23,126								11,515
42400800	DETECTABLE WARNINGS	SQ FT	536		536								
44000100	PAVEMENT REMOVAL	SQ YD	19,816		19,816								
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,503		2,503								
44000300	CURB REMOVAL	FOOT	253		253								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	8,474		8,474								
44000600	SIDEWALK REMOVAL	SQ FT	32,837		32,837								
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	40									40	
44003100	MEDIAN REMOVAL	SQ FT	1,085		1,085								
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	214		214								
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	34		34								
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	68		68								
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	97		97								
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	351		351								