



## EROSION CONTROL LEGEND

	PERMANENT LANDSCAPING (SEE NOTE 3)	$\boxtimes$	INLET FILTER
	PERMANENT LANDSCAPING INSTALLED IN PREVIOUS STAGE (SEE NOTE 3)	$\boxtimes$	INLET FILTER INSTALLED IN PREVIOUS STAGE
	TEMPORARY PAVEMENT	27)	PERMANENT DRAINAGE STRUCTURE NUMBER (SEE NOTE 5)
	SEDIMENT CONTROL, SILT FENCE (SEE NOTE 2)		PROPOSED STORM SEWER (SEE NOTE 5)
	SEDIMENT CONTROL, SILT FENCE INSTALLED IN PREVIOUS STAGE		TEMPORARY PIPE CULVERT
С	DRAINAGE STRUCTURE TO BE CLEANED	— xxx —— xxx -	TEMPORARY CONSTRUCTION FENCE

## NOTES

- 1. THE CONSTRUCTION LIMITS WILL BE STAKED BY THE ENGINEER
  PRIOR TO COMMENCING CONSTRUCTION. THE CONSTRUCTION LIMITS
  MAY BE ADJUSTED BY THE ENGINEER TO PRESERVE TREES. NO
  ADDITIONAL COMPENSATION WILL BE PAYMENT WILL BE MADE TO THE
  CONTRACTOR FOR CHANGES TO THE CONSTRUCTION LIMITS.
- SEDIMENT CONTROL, SILT FENCE SHALL BE ERECTED ADJACENT TO R.O.W., EASEMENT, AND CONTRUCTION LIMITS AND AS DIRECTED BY THE ENGINEER.
- 3. SEE LANDSCAPING PLANS FOR LANDSCAPING REQUIREMENTS.
- 4. SEE STAGE 3 TO 5 OF THE CROSS SECTIONS FOR GRADING INFORMATION.
- 5. SEE PROPOSED DRAINAGE PLANS FOR STORM SEWER INFORMATION.
- 6. REQUIRED ADJUSTMENT AND/OR RECONSTRUCTION OF THE PROPOSED STRUCTURE TO FINAL RIM ELEVATION SHALL NOT BE PAID FOR SEPARATELY. THE COST FOR THIS WORK SHALL BE INCLUDED IN THE COST OF THE PROPOSED STRUCTURE.

50	0		50	100
	SCALE	IN	FEET	

FILE NAME =	USER NAME = \$USER\$	DESIGNED - PJO	REVISED -		ILLINOIS ROUTE 59	F.A. SECTION COUNTY TOTAL SHEET
\$FILEL\$		DRAWN - RTA	REVISED -	STATE OF ILLINOIS	EROSION CONTROL - STAGE 3 THRU 5	338 113 N-2 WILL <b>260 157</b>
	PLOT SCALE = \$SCALE\$	CHECKED - JCM	REVISED -	DEPARTMENT OF TRANSPORTATION	ENUSION CONTROL - STAGE 3 THRO 3	CONTRACT NO. 60E73
	PLOT DATE = \$DATE\$	DATE - JANUARY 16, 2009	REVISED -		SCALE: AS SHOWN SHEET NO. 2 OF 4 SHEETS STA. 3337+00 TO STA. 3351+00	FED. ROAD DIST. NO. ILLINOIS FAP 338 (IL RTE. 59)