

## EROSION CONTROL LEGEND

PERMANENT LANDSCAPING (SEE NOTE 3)

PERMANENT LANDSCAPING INSTALLED
IN PREVIOUS STAGE (SEE NOTE 3)

TEMPORARY PAVEMENT

SEDIMENT CONTROL, SILT FENCE (SEE NOTE 2)

SEDIMENT CONTROL, SILT FENCE
INSTALLED IN PREVIOUS STAGE

TEMPORARY PIPE CULVERT

TEMPORARY PIPE CULVERT

TEMPORARY PIPE CULVERT

TEMPORARY CONSTRUCTION FENCE

DRAINAGE STRUCTURE TO BE CLEANED

- 1. THE CONSTRUCTION LIMITS WILL BE STAKED BY THE ENGINEER PRIOR TO COMMENCING CONSTRUCTION. THE CONSTRUCTION LIMITS MAY BE ADJUSTED BY THE ENGINEER TO PRESERVE TREES. NO ADDITIONAL COMPENSATION WILL BE PAYMENT WILL BE MADE TO THE CONTRACTOR FOR CHANGES TO THE CONSTRUCTION LIMITS.
- 2. SEDIMENT CONTROL, SILT FENCE SHALL BE ERECTED ADJACENT TO R.O.W., EASEMENT, AND CONTRUCTION LIMITS AND AS DIRECTED BY THE ENGINEER.
- 3. SEE LANDSCAPING PLANS FOR LANDSCAPING REQUIREMENTS.
- 4. SEE STAGE 3 TO 5 OF THE CROSS SECTIONS FOR GRADING INFORMATION.
- 5. SEE PROPOSED DRAINAGE PLANS FOR STORM SEWER INFORMATION.
- 6. REQUIRED ADJUSTMENT AND/OR RECONSTRUCTION OF THE PROPOSED STRUCTURE TO FINAL RIM ELEVATION SHALL NOT BE PAID FOR SEPARATELY. THE COST FOR THIS WORK SHALL BE INCLUDED IN THE COST OF THE PROPOSED STRUCTURE.

50	0	50	100
	SCALE II	N FEET	

FILE NAME	=	USER NAME = \$USER\$	DESIGNED -	PJ0	REVISED -		U.S. ROUTE 30	F.A. RTF.	SECTION	COUNTY	TOTAL SHEET
\$FILEL\$			DRAWN -	RTA	REVISED -	STATE OF ILLINOIS	EROSION CONTROL – STAGE 3 THRU 5	338	113 N-2	WILL	260 159
		PLDT SCALE = \$SCALE\$	CHECKED -	JCM	REVISED -	DEPARTMENT OF TRANSPORTATION	ENOSION CONTINCE - STAGE 3 TIMO 3			CONTRACT NO	60E73
		PLOT DATE = \$DATE\$	DATE -	JANUARY 16, 2009	REVISED -		SCALE: AS SHOWN   SHEET NO. 4 OF 4 SHEETS   STA. 3760+00 TO STA. 3771+00	FED. ROAD D	IST. NO. ILLINOIS	FAP 338 (IL	RTE. 59)