

D-91-031-09

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	OUTSIDE/INSIDE SHOULDERS					CODE NO	ITEM	UNIT	TOTAL QUANTITIES					
				100% STATE URBAN SFTY-2A													
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	27	27													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4													
67100100	MOBILIZATION	L SUM	1	1													
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	54305	54305													
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	12585	12585													
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	4975	4975													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	31470	31470													
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	54305	54305													
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	12585	12585													
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	4975	4975													
78300100	PAVEMENT MARKING REMOVAL	SQ FT	31470	31470													
X0325223	FIBER ASPHALT	POUND	2037	2037													
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1													
XZ186500	ASPHALTIC EMULSION SLURRY SEAL	SQ YD	65200	65200													
X0326218	FIBER-MODIFIED ASPHALT CRACK SEALING	FOOT	6110	6110													
X0326219	BUMP REMOVAL	EACH	460	460													

* SPECIALITY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI 290/I-290 EB)
 25TH AVENUE TO I-90/94
 SUMMARY OF QUANTITIES

RAL