

SUMMARY OF QUANTITIES				URBAN 100% FED.	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	18	18	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30	30	
40600300	AGGREGATE (PRIME COAT)	TON	165	165	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40	
40600535	LEVELING BINDER (HAND METHOD), N70	TON	30	30	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	575	575	
40600990	TEMPORARY RAMP	SQ YD	750	750	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,400	3,400	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	15	15	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	250	250	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	38,800	38,800	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	15	15	
44000600	SIDEWALK REMOVAL	SQ FT	250	250	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300	
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	600	600	
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	420	420	
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	130	130	
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	1,300	1,300	
60252800	CATCH BASIN TO BE RECONSTRUCTED	EACH	5	5	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	5	5	
60262700	INLETS TO BE RECONSTRUCTED	EACH	5	5	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	85	85	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	

• DENOTES SPECIALTY ITEM

NP = Non-participating

SUMMARY OF QUANTITIES				URBAN 100% FED.	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,590	2,590	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,350	1,350	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	50,700	50,700	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	7,800	7,800	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,530	1,530	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,100	2,100	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,320	1,320	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9,400	9,400	
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	450	450	
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16,900	16,900	
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,600	2,600	
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	510	510	
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	700	700	
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	440	440	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	700	700	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	665	665	
• 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,600	1,600	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,100	2,100	
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	85	85	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

FILE NAME = N:\PROJ\3329\3329_45\Design\Proposed\3329_45-03-Quantities.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = mready	DESIGNED MWR	REVISED -
	DRAWN MWR	REVISED -
PLOT SCALE = 1:8000' / IN.	CHECKED WBL	REVISED -
PLOT DATE = 2/4/2009	DATE 2/4/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US 12 / 45
PROSPECT AVENUE TO WALNUT AVENUE
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 465 X-RS-2	COUNTY COOK	TOTAL SHEETS 18	SHEET NO. 3
CONTRACT NO. 60F24				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT