

CONTRACT NO. 60F48

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
341.375	2326.IRS-1	COOK	30	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			100% FED	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES URBAN	I000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	260	260				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	77	77				
40600300	AGGREGATE (PRIME COAT)	TON	384	384				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	29	29				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	840	840				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	606	606				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	9388	9388				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	86623	86623				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3500	3500				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	3500	3500				
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	20830	20830				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	710	710				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	240	240				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	3450	3450				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	282	282				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	20	20				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2				
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5				
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	150	150				
60405420	FRAMES AND GRATES, TYPE B-18	EACH	1	1				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	10	10				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	65	65				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				

SUMMARY OF QUANTITIES			100% FED	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES URBAN	I000				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4380	4380				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1163	1163				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	35763	35763				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	10009	10009				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3336	3336				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1455	1455				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1163	1163				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	35763	35763				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	10009	10009				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3336	3336				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1455	1455				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1700	1700				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1500	1500				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2713	2713				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	3772	3772				
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	819	819				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
0 Z0076600	TRAINEES	HOUR	1,000	1,000				

© 4080  
\* Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
TOUHY AVE.

PLOT DATE: 2/2/2009

2/2/2009 9:58:42 AM D:\KELLER\BMS94228107509-SHT-PLAN.DWG