

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE (WEST FRONTAGE ROAD)	BRIDGE (EAST FRONTAGE ROAD)	CONSTRUCTION TYPE CODE (100% STATE)													
				1000-2A	X281-2A	X281-2A														
50200100	STRUCTURE EXCAVATION	CU YD	110	0	60	50														
50300225	CONCRETE STRUCTURES	CU YD	133.5	0.0	69.7	63.8														
50300255	CONCRETE SUPERSTRUCTURE	CU YD	437.4	0.0	248.9	188.5														
50300260	BRIDGE DECK GROOVING	SQ YD	1,197	0	615	582														
50300300	PROTECTIVE COAT	SQ YD	1,559	0	864	695														
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	5,786	0	3,192	2,594														
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	110,060	0	59,320	50,740														
50800515	BAR SPLICERS	EACH	162	0	96	66														
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	164.0	0.0	97.5	66.5														
51500100	NAME PLATES	EACH	2	0	1	1														
52000110	PREFORMED JOINT STRIP SEAL	FOOT	88	0	48.5	39.5														
58700300	CONCRETE SEALER	SQ FT	1,442	0	801	641														
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	18	18	0	0														
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5	0	0														
60405740	FRAMES AND GRATES TO BE REMOVED	EACH	2	2	0	0														
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2	0	0														
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,244	1,244	0	0														
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	876	876	0	0														
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	3,577	3,577	0	0														
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	115	115	0	0														
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	0	0														
63200310	GUARDRAIL REMOVAL	FOOT	103	103	0	0														
66400505	CHAIN LINK FENCE, 8'	FOOT	275	275	0	0														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	0	0														
67100100	MOBILIZATION	L SUM	1	1	0	0														
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	0	0														
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	0	0														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,582	1,582	0	0														
72000100	SIGN PANEL - TYPE 1	SQ FT	25.5	25.5	0.0	0.0														
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1	0	0														
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	77.5	77.5	0.0	0.0														
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	233.9	233.9	0.0	0.0														
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	14	14	0	0														
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	2	2	0	0														

\* SPECIALTY ITEM

FILE NAME =  
G:\project\2082305\CADD\Civil\Sheet\03\03PLM\_LM\_01.dgn

USER NAME = zpiend  
PLOT SCALE = 5/8" = 1' / IN.  
PLOT DATE = 3/6/2009

DESIGNED - DLP  
DRAWN - ENTRAN  
CHECKED - TMH  
DATE - 1/09

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**WEST AND EAST FRONTAGE ROADS  
SUMMARY OF QUANTITIES**

SCALE: 1"=50'      SHEET NO. OF SHEETS      STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	1415 B	COOK	75	4
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		CONTRACT NO. 60F60