SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE (WEST FRONTAGE ROAD)	BRIDGE (EAST FRONTAGE ROAD)								
					CONSTRUCTION TYPE CODE (100% STATE)										
					1000-2A	X281-2A	X281-2A								
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	320	320	0	0								
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	500	500	0	0								
*	78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	1,324	1,324	0	0								
*	78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	415	415	0	0								
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	24	24	0	0								
*	78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	4	4	0	0								
*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	16	16	0	0								
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1	0	0								
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	80	80	0	0								
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	24	24	0	0								
*	B2000362	TREE, ACER GINNALA FLAME (FLAME AMUR MAPLE), 4' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	10	10	0	0								
*	C2011830	SHRUB, VIBURNUM DENTATUM MORTON (NORTHERN BURGUNDY ARROWWOOD VIBURNUM), 2-1/2' HEIGHT, BALLED AND BURLAPPED	EACH	100	100	0	0								
	X0321472	REMOVE TEMPORARY CONCRETE BARRIER	FOOT	60	60	0	0								
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	32	32	0	0								
	X0325236	BICYCLE RAILING TO BE REMOVED AND REINSTALLED	FOOT	66.5	0.0	66.5	0.0								
	X0712400	TEMPORARY PAVEMENT	SQ YD	779	779	0	0								
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	2	2	0	0								
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1	0	0								
	X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	649.6	0.0	357.1	292.5								
	X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1	0	0								
	X7030104	WET TEMPORARY PAVEMENT MARKING TAPE , TYPE III, 4 INCH	FOOT	3,706	3,706	0	0								
	X7030108	WET TEMPORARY PAVEMENT MARKING TAPE , TYPE III, 8 INCH	FOOT	374	374	0	0								
	X7030112	WET TEMPORARY PAVEMENT MARKING TAPE , TYPE III, 12 INCH	FOOT	61	61	0	0								
	X7030124	WET TEMPORARY PAVEMENT MARKING TAPE , TYPE III, 24 INCH	FOOT	19	19	0	0								
	XX001758	WOOD FENCE REMOVAL	FOOT	32	32	0	0								
	XX006571	REMOVE AND REPLACE BOLLARDS	EACH	14	14	0	0								
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	3,407	3,407	0	0								
	Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	52	0	26	26								
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	0	0								
	Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1	1	0	0								
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	0	0								

* SPECIALTY ITEM

FILE NAME = G:\project\2082305\CADD\Civil\Sht\003\003PLMLSM_01.dgn	USER NAME = 2pierad	DESIGNED - DLP	REVISED -
		DRAWN - ENTRAN	REVISED -
	PLOT SCALE = 50.00 ' / IN.	CHECKED - TMH	REVISED -
	PLOT DATE = 2/4/2009	DATE - 1/09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WEST AND EAST FRONTAGE ROADS
SUMMARY OF QUANTITIES

SCALE: 1"=50' | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	1415 B	COOK	75	5
		CONTRACT NO. 60F60		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		