

ROUTE: IL 47 (MAIN ST. TO IL 176 AND IL 120 TO CHARLES RD.)

CROSS STREETS		DIRECTION (EB/WB (NB/SB))	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	PATCH AREA (SQ FT)	PATCH AREA (SQ YD)
FROM	TO						
Main St (Huntley) - 0.1 mi	ROUTE 176	NB	1	12	6	72	8
Main St (Huntley) - 3.6 mi	ROUTE 176	NB	1	12	60	720	80
Main St (Huntley) - 4.4 mi	ROUTE 176	NB	1	6	6	36	4
Rte 176 S. Leg - 1.6 mi	ROUTE 14	Center Line	1	2	100	200	22
Rte 176 S. Leg - 2.5 - 2.6 mi	ROUTE 14	Center Line	1	2	528	1056	117
Rte 176 S. Leg - 2.9 - 3.0 mi	ROUTE 14	Wheel Lane	1	2	528	1056	117
Rte 14 - 0.1 mi	Charles Rd	NB	1	12	6	72	8
Rte 14 - 0.5 - 0.6 mi	Charles Rd	Wheel Lane	1	2	528	1056	117
Rte 14 - 0.5 mi	Charles Rd	NB	Lt Turn	12	6	72	8
Rte 14 - 0.5 mi	Charles Rd	NB	1	12	6	72	8
Rte 14 - 0.7 mi	Charles Rd	Wheel Lane	1	2	50	100	11
Rte 14 - 0.9 mi	Charles Rd	NB	1	12	12	144	16
Rte 14 - 1.0 mi	Charles Rd	Wheel Lane	1	6	12	72	8
Rte 14 - 1.05 mi	Charles Rd	Wheel Lane	1	6	12	72	8
Rte 14 - 1.1 mi	Charles Rd	NB	1	6	12	72	8
Rte 14 - 1.2 - 1.3 mi	Charles Rd	Wheel Lane Rt	1	2	528	1056	117
Rte 14 - 1.2 - 1.3 mi	Charles Rd	Wheel Lane Lt	1	2	528	1056	117
Rte 14 - 1.5 mi	Charles Rd	Wheel Lane	1	2	100	200	22
Rte 14 - 1.7 mi	Charles Rd	NB	1	12	6	72	8
Rte 14 - 1.8 mi	Charles Rd	NB	1	12	6	72	8
Rte 14 - 2.0 mi	Charles Rd	Wheel Lane Rt	1	2	25	50	6
Rte 14 - 2.0 mi	Charles Rd	Wheel Lane Lt	1	2	25	50	6
Rte 120 - 0.2 mi	ROUTE 14	SB	1	12	12	144	16
Rte 120 - 0.5 mi	ROUTE 14	SB	1	6	12	72	8
Rte 120 - 0.7 - 0.8 mi	ROUTE 14	Center Line	1	2	528	1056	117
Rte 120 - 0.9 mi	ROUTE 14	SB	1	12	12	144	16
Rte 120 - 1.1 mi	ROUTE 14	Wheel Lane	1	2	50	100	11
Rte 120 - 1.3 - 1.4 mi	ROUTE 14	Wheel Lane	1	2	528	1056	117
Rte 120 - 1.7 mi	ROUTE 14	SB	1	6	12	72	8
Rte 176 S leg - .4	Huntley Main St	SB	1.0	4	12	48	5
Rte 176 S leg - .4	Huntley Main St	SB	1.0	4	12	48	5
Rte 176 S leg - .9	Huntley Main St	SB	1.0	4	14	56	6
Rte 176 S leg - 2.2	Huntley Main St	SB Rt Wheel	1.0	6	12	72	8
Rte 176 S leg - 2.2	Huntley Main St	SB Rt Wheel	1.0	4	15	60	7
Rte 176 S leg - 2.4	Huntley Main St	SB Rt Wheel	1.0	4	15	60	7
Rte 176 S leg - 5.1	Huntley Main St	SB	1.0	4	12	48	5
Huntley Main St - .8	Rte 176 S leg	NB	1.0	4	13	52	6
Huntley Main St - 4.5	Rte 176 S leg	NB RT Wheel	1.0	4	20	80	9
Huntley Main St - 5.0	Rte 176 S leg	NB RT Wheel	1.0	4	10	40	4
Rte 176 S leg - 1.1	Rte 14	NB	1.0	12	30	360	40
Rte 176 S leg - 2.0	Rte 15	Center Jt	1.0	2	100	200	22
Rte 176 S leg - 2.1	Rte 16	Center Jt	1.0	2	100	200	22
Rte 176 S leg - 2.3	Rte 17	NB	1.0	6	12	72	8
TOTALS					4621 SF	1274 SY	

RESURFACING TO BE DONE WITHIN NEW PROJECT LIMITS ONLY OR AS DIRECTED BY THE ENGINEER. LOCATIONS TO BE DETERMINED IN THE FIELD BY THE ENGINEER.

FILE NAME *	USER NAME = wilgreendp	DESIGNED -	REVISED - DW - 4/8/09
o:\p\work\p\W001\WILGREENDP\40125947\stgn.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000 / / IN.		CHECKED -	REVISED -
PLOT DATE = 4/8/2009		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE			
IL 47			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-020 PP	MCHENRY	25	14
CONTRACT NO. 60G19				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				