

ROUTE: US. RTE 30 (US 34 TO BRIARCLIFF)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR	
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)	
WEST OF GOODWIN	BOX CULVERT APPROACH	WB & EB	1	22	40	880	98	
	CULVERT DECK IN POOR	EB& WB	1	22	50	1100	122	
	CENTER LINE JOINT			2	160	320	36	
		EB&WB	1	22	10	220	24	
		WB&EB	1	22	30	660	73	
		EB	1	11	20	220	24	
		EB	1	11	10	110	12	
		EB	1	11	10	110	12	
		EB	1	11	10	110	12	
		WB	1	11	10	110	12	
		CENTER LINE JOINT			2	300	600	67
		WB&EB	1	22	18	396	44	
		EB & WB	1	22	10	220	24	
		WB	1	11	10	110	12	
		WB & EB	1	11	10	110	12	
	CENTER LINE JOINT			2	300	600	67	
	WB & EB	1	22	10	220	24		
	WB & EB	1	22	30	660	73		
WEST OF GOODWIN	NORTH EDGE OF SHOULDER	WB & EB	1	6	300	1800	200	
		EB&WB	1	22	40	880	98	
		WB	1	11	20	220	24	
		EB	1	11	50	550	61	
		EB	1	11	30	330	37	
		EB	1	11	30	330	37	
		EB	1	11	20	220	24	
		WB	1	11	40	440	49	
		EB	1	11	20	220	24	
		WB & EB	1	22	20	440	49	
		WB&EB	1	22	18	396	44	
		CENTER LINE JOINT			2	360	720	80
		WB & EB	1	11	60	660	73	
		WB & EB	1	22	30	660	73	
		WB & EB	1	22	20	440	49	
	MEDIAN LANE 6' - 11' AND	WB & EB	1	11	250	2750	306	
	WB & EB	1	22	40	880	98		
WEST OF GOODWIN		EB	1	11	20	220	24	
		EB	1	11	20	220	24	
30' EAST OF 5TH ST		WB & EB	1	22	20	440	49	
40' EAST OF 5TH ST		WB & EB	1	11	30	330	37	
50' EAST OF 5TH ST	NORTH SHOULDER	WB	1	10	36	360	40	
		EB/WB &	1	33	30	990	110	
		EB/WB &	1	33	10	330	37	
		EB/WB &	1	33	12	396	44	
200' EAST OF DOUGLASS		EB/WB &	1	33	10	330	37	
220 EAST OF DOUGLASS		EB/WB &	1	11	10	110	12	
240 EAST OF DOUGLASS		EB/WB &	1	22	20	440	49	
100' EAST OF DOUGLASS			1	33	20	660	73	
WEST OF DOUGLASS	BRIAR CLIFF	EB/WB &		33	12	396	44	
		EB/WB &	1	33	12	396	44	
		EB/WB &	1	33	12	396	44	
		WB & EB	1	22	12	264	29	
		WB & EB	1	22	12	264	29	
		WB & EB	1	22	12	264	29	
		WB & EB	1	22	12	264	29	
		EB & WB	1	22	12	264	29	
		EB & WB	1	22	12	264	29	
		EB	1	11	80	880	98	
WEST OF DOUGLASS	BRIAR CLIFF	EB & WB	1	22	12	264	29	
		EB & WB	1	22	12	264	29	
		EB	1	11	80	880	98	
		WB & EB	1	22	12	264	29	
		EB & WB	1	22	12	264	29	
		EB & WB	1	22	12	264	29	
		EB & WB	1	33	12	396	44	
		EB & WB	1	22	12	264	29	
		EB	1	11	12	132	15	
		EB	1	11	12	132	15	

TOTAL 2924 FT 3278 SY

FILE NAME =	USER NAME = smythk1	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PATCHING SCHEDULE US 30</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pvc\work\pavdot\smythk1\09125057\Design	DRAWN -	REVISED -	VAR.					2009-021 PP	DUPAGE	32	22	
PLOT SCALE = 1/8" = 1' / IN.	CHECKED -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 60G20				
PLOT DATE = 2/5/2009	DATE -	REVISED -	FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT									