

CONTRACT NO. 60G25

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% FED 1000-2A			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6			
40600300	AGGREGATE (PRIME COAT)	TON	28	28			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	41	41			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	541	541			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1574	1574			
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	13,513	13,513			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3			
67100100	MOBILIZATION	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8497	8497			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2833	2833			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	250	250			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	46730	46730			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1000	1000			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200	200			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	490	490			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	490	490			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1000	1000			
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	720	720			
© 20076600	TRAINEES	HOUR	1500	1500			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES				

\* SPECIALTY ITEMS  
© Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

Rev. 4-9-09

PLOT DATE: 2/6/2009