

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-026 PP	COOK	30	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
CONTRACT NO. 60G25				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 100%	FED	1000-2A			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	7					
40600300	AGGREGATE (PRIME COAT)	TON	33	33					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	50	50					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	655	655					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1833	1833					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	16358	16358					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8497	8497					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2833	2833					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	250	250					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	46730	46730					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1000	1000					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200	200					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	490	490					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	490	490					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1000	1000					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	823	823					
© 20076600	TRAINEEES	HOUR	1500	1500					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT							

* SPECIALTY ITEMS
© Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 2/6/2009

2/6/2009 8:03:00 AM User:wilgreendp