

Drawing file: W:\Projects\61208192 - Canfield Ave LAPP\SUMMO1.dwg Feb 04, 2009 - 4:03pm

CODE	PAY ITEM	UNIT	I000	
			TOTAL QUANTITY	80% FEDERAL 20% VILLAGE
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQYD	600	600
25200100	SODDING	SQYD	600	600
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	950	950
40600300	AGGREGATE (PRIME COAT)	TON	20	20
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQYD	215	215
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N50	TON	820	820
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQYD	150	150
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQFT	6,010	6,010
42400800	DETECTABLE WARNINGS	SQFT	90	90
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQYD	8,900	8,900
44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	255	255
44000600	SIDEWALK REMOVAL	SQFT	6,150	6,150
44001700	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	185	185
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQYD	100	100
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQYD	50	50
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	6	6
67100100	MOBILIZATION	L SUM	1	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,500	2,500
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQFT	40	40
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,500	1,500
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	900	900
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	340	340
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	150	150
88600600	DETECTOR LOOP REPLACEMENT	FOOT	80	80
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	425	425
XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQYD	225	225

*
*
*
*
*
*

DENOTES SPECIALTY ITEM



USER NAME -- XX	DESIGNED -- JGG	REVISED -- XX
PLOT SCALE -- XX	DRAWN -- MK	REVISED -- XX
PLOT DATE -- XX	CHECKED -- XX	REVISED -- XX
	DATE -- 01-02-2009	REVISED -- XX

**CANFIELD AVENUE IMPROVEMENT (LAPP)
VILLAGE OF NORRIDGE, ILLINOIS**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 4 OF 13 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2763	08-00055-00-RS	COOK	13	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63120	