

SUMMARY OF QUANTITIES

PLAN	SURVEYED	DATE
NOTE BOOK	PLOTTED	BY
NO.	BY	
	PLANNED	
	BY	
	PLANNED	
	BY	

PROFILE	SURVEYED	DATE
NOTE BOOK	PLOTTED	BY
NO.	BY	
	PLANNED	
	BY	
	PLANNED	
	BY	

CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	ROADWAY 1000-2A		LIGHTING Y030-1E		UTILITY ADJUSTMENT Y060	
				PARTICIPATING	NON-PARTICIPATING	PARTICIPATING	NON-PARTICIPATING	PARTICIPATING	NON-PARTICIPATING
40701801	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 6"	SO YD	8,917	8,917					
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SO YD	162	162					
42001300	PROTECTIVE COAT	SO YD	3,924	3,924					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	35	35					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SO FT	25,198	25,198					
42400800	DETECTABLE WARNINGS	SO FT	136	136					
44000100	PAVEMENT REMOVAL	SO YD	6,749	6,749					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	1,997	1,997					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	391	391					
44000600	SIDEWALK REMOVAL	SO FT	12,668	12,668					
54214077	ALUMINUM END SECTIONS 12"	EACH	5	5					
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 12"	FOOT	1,092	1,092					
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 15"	FOOT	146	146					
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 18"	FOOT	474	474					
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 24"	FOOT	941	941					
55022100	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 27"	FOOT	142	142					
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 30"	FOOT	408	408					
55023700	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV, 12"	FOOT	6	6					
55024300	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV, 30"	FOOT	12	12					
* 56105200	WATER VALVES, 12"	EACH	8						8
* 56200300	WATER SERVICE LINE 1"	FOOT	873						873
* 56400500	FIRE HYDRANTS TO BE REMOVED	EACH	6						6
* 56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	10						10

* INDICATES SPECIALTY ITEM
 Δ INDICATES SPECIAL PROVISION

FILE NAME =	USER NAME = #USER#
#FILE#	

DESIGNED - JAB	REVISIONS
DRAWN - JAB	REVISIONS -
CHECKED - JMT	REVISIONS -
DATE - 01/02/09	REVISIONS -

PLCT SCALE = #SCALE#	PLCT DATE = #DATE#

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: NONE	SHEET NO. 2	OF 6 SHEETS	STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3003	00-00084-00-PV	DUPAGE	112	5
BLACKHAWK DR RECONSTRUCTION			CONTRACT NO. 63121	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				