

SUMMARY OF QUANTITIES

SP	CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	ROADWAY IC00-2A		LIGHTING Y030-1E		UTILITY ADJUSTMENT Y060	
					PARTICIPATING	NON-PARTICIPATING	PARTICIPATING	NON-PARTICIPATING	PARTICIPATING	NON-PARTICIPATING
△	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,000	2,000					
	72000100	SIGN PANEL - TYPE 1	SQ FT	8	8					
	72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	181	181					
	72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	161	161					
	72900100	METAL POST - TYPE A	FOOT	240	240					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	37	37					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,549	3,549					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	908	908					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	395	395					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	125	125					
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	272	272					
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1			
*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1			1			
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	450			450			
* △	81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	857			857			
*	81400100	HANDHOLE	EACH	2			2			
*	81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	10,340			10,340			
*	81702190	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4/0	FOOT	1,350			1,350			
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,728			1,728			
*	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	16			16			
*	83007300	LIGHT POLE, ALUMINUM, 35 FT. M.H., 8 FT. MAST ARM	EACH	16			16			
*	83600360	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 10" X 6"	EACH	16			16			
*	84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	3			3			
* △	84200700	LIGHTING FOUNDATION REMOVAL	EACH	3			3			
	550B0050	STORM SEWERS, CLASS B, TYPE 1, 12", PVC	FOOT	561	561					
	550B0070	STORM SEWERS, CLASS B, TYPE 1, 15", PVC	FOOT	13	13					
*	B2000116	TREE, ACER CAMPESTRE (HEDGE MAPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	24	24					

* INDICATES SPECIALTY ITEM
 △ INDICATES SPECIAL PROVISION

PLAN SURVEYED BY DATE
 PLOTTED BY DATE
 NOTE BOOK NO. OF MAY CHECKED
 SAID FILE NAME

PROFILE SURVEYED BY DATE
 PLOTTED BY DATE
 NOTE BOOK NO. OF MAY CHECKED
 STRUCTURE METATINS CHECKED