


ILE NAME

FTI FI &

JSER NAME = \$USER\$

LOT SCALE = #SCALE#




NOTES:

- 1. WHEN PLACED INTO SERVICE, CONDUIT SHALL BE SEALED WITH CONDUIT DUCT SEAL COMPOUND AT EACH END.
- 2.6" WIDE REINFORCED METALLIC WARNING TAPE WITH RED AND BLACK LETTERING TO READ "CAUTION- ELECTRICAL LINE BURIED BELOW." WARNING TAPE TO BE PLACED 1' MINIMUM TO 2' MAXIMUM BELOW FINISHED GRADE.
- 3. ALL TURF AREAS DISTURBED DURING CONSTRUCTION SHALL BE RESTORED WITH 4" OF TOPSOIL AND SOD, INCLUDED IN THE COST OF TRENCH AND BACKFILL FOR ELECTRICAL WORK.


TYPICAL CONDUIT TRENCH DETAIL

NOT TO SCALE



SPLICING ELECTRIC CABLES BASIC MATERIALS & METHODS

NOT TO SCALE



GROUND FIELD DETAIL NOT TO SCALE

DESIGNED - FEI	REVISED -			F.A.U SECTION	COUNTY TOTAL SHEET
DRAWN ~ TMC	REVISED -	STATE OF ILLINOIS	ELECTRICAL DETAILS	3003 00-00084-00	D-PV DUPAGE 112 69
CHECKED - MAR	REVISED -	DEPARTMENT OF TRANSPORTATION		BLACKHAWK DR RECONSTI	RUCTION CONTRACT NO. 63121
DATE - 01/02/09	REVISED -		SCALE: NONE SHEET NO. 2 OF 3 SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1 ILLIN	NOIS FED. AID PROJECT