



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 10, 2009

SUBJECT: FAU 1485 (Diehl Road)  
Project HSIP-8003(954)  
Section 08-00263-01-SP  
DuPage County  
Contract No. 63122  
Item 104  
April 24, 2009 Letting  
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

**Proposal – Removed special provision COMPLETION DATE PLUS WORKING DAYS and updated LR 107-4.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll  
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "DE" monogram.

By: Ted B. Walschleger  
Engineer of Project Development  
and Implementation

**SPECIAL PROVISIONS**

**TABLE OF CONTENTS**

|  | Page          |
|--|---------------|
| LOCATION OF PROJECT.....   | 2             |
| DESCRIPTION OF PROJECT .....   | 2             |
| START OF WORK.....   | 2             |
| SECTION 107 LEGAL REGULATIONS AND RESPONSIBILITY TO PUBLIC.....  | 3             |
| SECTION 108 PROSECUTION AND PROGRESS .....   | 3             |
| SECTION 109 MEASUREMENT AND PAYMENT.....   | 3             |
| SECTION 358 REPAIR AND PREPARATION OF BASE COURSE.....   | 3             |
| SECTION 406 HOT-MIX ASPHALT BINDER AND SURFACE COURSE.....   | 4             |
| SECTION 602 CATCH BASIN, MANHOLE, INLET, DRAINAGE STRUCTURE, VALVE VAULT<br>CONSTRUCTION, ADJUSTMENT AND RECONSTRUCTION..... | 4             |
| SECTION 703 WORK ZONE PAVEMENT MARKING.....  | 5             |
| PORTABLE CHANGEABLE MESSAGE SIGNS.....   | 5             |
| MAINTENANCE OF ROADWAYS.....   | 5             |
| STATUS OF UTILITIES TO BE ADJUSTED.....  | 7             |
| USE OF MULTIPLE CONCRETE PLANTS IN THE SAME CONSTRUCTION ITEM .....  | 8             |
| USE OF RAP (dist 1).....   | 10            |
| TRAFFIC SIGNAL SPECIFICATIONS FOR DETECTOR REPLACEMENT AND/OR .....  | 18            |
| INSTALLATION ON ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS.....  | 18            |
| CLASS D PATCHES TYPES IV, 12 INCH .....  | 23            |
| TRAFFIC CONTROL PLAN.....  | 24            |
| UTILITY STRUCTURES TO BE ADJUSTED.....   | 26            |
| CENTER LINE - RUMBLE STRIP .....   | 27            |
| PAVEMENT PATCHING (PARTIAL DEPTH).....   | 27            |
| SAG FRAME AND LID .....  | 28            |
| COMBINATION CONCRETE CURB AND GUTTER REMOVAL & REPLACEMENT .....   | 29            |
| RAISED REFLECTIVE PAVEMENT MARKER REMOVAL .....  | 30            |
| RECESSED REFLECTIVE PAVEMENT MARKERS .....   | 30            |
| FINE AGGREGATE FOR HOT-MIX ASPHALT (HMA) (DISTRICT ONE).....   | 32            |
| TEMPERATURE CONTROL FOR CONCRETE PLACEMENT (DISTRICT ONE).....   | 32            |
| HOT MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (D-1).....  | 32            |
| <del>COMPLETION DATE PLUS WORKING DAYS .....</del>   | <del>34</del> |

*Deleted  
4-10-09*

*Revised 4-10-09*

1030.05(d) (4) Replace the density control limits table with the following:

| DENSITY CONTROL LIMITS     |              |                               |                             |
|----------------------------|--------------|-------------------------------|-----------------------------|
| Mixture Composition        | Parameter    | Individual Test <sup>2/</sup> | Minimum Joint Density Value |
| IL-9.5, IL-12.5            | Ndesign ≥ 90 | 92.0 – 96.0 %                 | 90.0 %                      |
| IL-9.5, IL-9.5L, IL-12.5   | Ndesign < 90 | 92.5 – 97.4 %                 | 90.0 %                      |
| IL-19.0, IL-25.0           | Ndesign ≥ 90 | 93.0 – 96.0 %                 | 90.0 %                      |
| IL-19.0, IL-19.0L, IL-25.0 | Ndesign < 90 | 93.0 – 97.4 %                 | 90.0 %                      |
| All Other                  | Ndesign = 30 | 93.0 <sup>1/</sup> - 97.4 %   | 90.0 %                      |

- 1/ 92.0 % when placed as first lift on an unimproved subgrade.  
 2/ "Density values" shall meet the "Individual Test" density control limits specified herein.

~~COMPLETION DATE PLUS WORKING DAYS~~

Deleted 4-10-09 \*

Effective: September 30, 1985  
 Revised: January 1, 2007

Revise Article 108.05 (b) of the Standard Specifications as follows:

"When a completion date plus working days is specified, the Contractor shall complete all contract items and safely open all roadways to traffic by 11:59 PM on August 28, 2009 except as specified herein.

The Contractor will be allowed to complete all clean-up work and punch list items within 0 working days after the completion date for opening the roadway to traffic. Under extenuating circumstances the Engineer may direct that certain items of work, not affecting the safe opening of the roadway to traffic, may be completed within the working days allowed for clean up work and punch list items. Temporary lane closures for this work may be allowed at the discretion of the Engineer.

(\*The completion date for resurfacing shall be August 28, 2009.)"

Revised 4-10-09

Diehl Road  
Section 08-00263-01SP  
Project No. HSIP-8003 (954)  
DuPage County, Illinois  
Contract #63122

*Deleted  
4-10-09*

~~Article 108.09 or the Special Provision for "Failure to Complete the Work on Time", if included in this contract, shall apply to both the completion date and the number of working days.~~

*Revised 4-10-09*

State of Illinois  
Department of Transportation  
Bureau of Local Roads and Streets

SPECIAL PROVISION  
FOR  
INSURANCE

Effective: February 1, 2007  
Revised: August 1, 2007

All references to Sections or Articles in this specification shall be construed to mean specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

The Contractor shall name the following entities as additional insured under the Contractor's general liability insurance policy in accordance with Article 107.27:

The City of Naperville

---

The City of Warrenville

---

DuPage County

---

HDR, Inc.

---

Thomas Engineering Group

---

---

The entities listed above and their officers, employees, and agents shall be indemnified and held harmless in accordance with Article 107.26.

Revised 4-10-09

39