

SUMMARY OF QUANTITIES

SPECIALTY ITEM	ITEM NUMBER	ITEM	UNIT	SQUARE BARN ROAD	HANSON ROAD	HUNTINGTON DRIVE	SANDBLOOM ROAD	TOTAL
				QUANTITY	QUANTITY	QUANTITY	QUANTITY	I000-2A QUANTITY
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	0	0	246	0	246
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	0	0	246	0	246
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	0	0	1109	0	1109
	21301048	EXPLORATION TRENCH 48" DEPTH	FOOT	0	0	45	0	45
	25200200	SUPPLEMENTAL WATERING	UNIT	5	5	5	5	20
	35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	72	94	143	25	334
	35800100	PREPARATION OF BASE	SQ YD	0	0	6720	0	6720
	35800200	AGGREGATE BASE REPAIR	TON	0	0	388	0	388
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20	20	20	20	80
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	3926	432	1519	1362	7239
	40600300	AGGREGATE (PRIME COAT)	TON	78	9	30	27	144
	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	0	0	334	0	334
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1540	169	0	559	2268
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1	1	1	4
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	0	0	966	0	966
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	67	0	1962	25	2054
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5130	565	0	2698	8393
	42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	115	0	150	45	310
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	0	0	148	83	231
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SQ FT	70	0	1000	50	1120
	42400800	DETECTABLE WARNINGS	SQ FT	144	0	240	66	450
	44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	4921	0	0	12970	17891
	44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	0	0	0	9665	9665
	44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	30772	3928	7750	0	42450
	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	0	0	6720	0	6720
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	390	0	580	295	1265
	44000600	SIDEWALK REMOVAL	SQ FT	70	0	1000	50	1120
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1400	210	640	560	2810
	44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	35693	3928	7750	12970	60341
	44000100	PAVEMENT REMOVAL, 10"	SQ YD	115	0	150	45	310
	44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	891	98	380	571	1940
	44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	891	98	380	571	1940
	44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	891	98	380	571	1940
	44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	891	98	380	571	1940
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	91	0	0	295	386
	67100100	MOBILIZATION	L SUM	0.25	0.25	0.25	0.25	1
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	0.25	0.25	0.25	0.25	1
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	0.25	0.25	0.25	0.25	1
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	0.25	0.25	0.25	0.25	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	0.25	0.25	0.25	0.25	1
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9100	1020	3090	6600	19810
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	438	37	255	260	990
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37200	4500	2600	27500	71800
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1985	180	2200	700	5065
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	900	0	1100	370	2370
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	100	60	305	115	580
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	0	0	1	0	1
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	0	0	600	0	600
	XX002258	STRUCTURES TO BE ADJUSTED	EACH	10	5	5	10	30
	XX003535	AGGREGATE BASE COURSE, TYPE B, 2"	SQ YD	0	0	148	83	231
	X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	0	0	1	0	1
	Z0013798	CONSTRUCTION LAYOUT	L SUM	0.25	0.25	0.25	0.25	1
	Z0017500	DRAINAGE & UTILITY STRUCTURE ADJUSTMENT (SPECIAL)	EACH	3	0	0	3	6
Δ	Z0076600	TRAINEES	HOUR	200	100	100	100	500

* SPECIALTY ITEMS
 Δ Y080

VILLAGE OF ALGONQUIN CONTACTS

PUBLIC WORKS DEPARTMENT
 110 MEYER DR.
 ALGONQUIN, IL 60102
 PHONE: 847-658-2754
 FAX: 847-658-2759

PUBLIC WORKS DIRECTOR
 ROBERT MITCHARD
 PHONE: x-402
 E-MAIL: ROBERTMITCHARD@ALGONQUIN.ORG

ASSISTANT DIRECTOR
 MICHELE ZIMMERMAN
 PHONE: x-401
 E-MAIL: MZIMMERMAN@ALGONQUIN.ORG

PUBLIC WORKS PROJECT MANAGER
 SHAWN M. HURTIG
 PHONE: x-403
 E-MAIL: SHAWN HURTIG@ALGONQUIN.ORG

STREET SUPERINTENDENT
 ALAN MOZOLA
 PHONE: x-410
 E-MAIL: ALANMOZOLA@ALGONQUIN.ORG

McHENRY COUNTY DIVISION OF TRANSPORTATION
 16111 NELSON ROAD
 WOODSTOCK, IL 60098

TRAFFIC ENGINEER
 BRADLEY J. COUSIN, P.E., PTOE
 PHONE: 815-334-4971
 FAX: 815-334-4989
 CELL: 815-482-2867
 E-MAIL: BJCOSIN@CO.MCHENRY.IL.US