



LEGEND

- HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH (3.2 INCHES TO 4.1 INCHES)
- HOT-MIX ASPHALT SURFACE REMOVAL, 3"
- HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"
- HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"
- SIDEWALK REMOVAL
- BUTT JOINT
- DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT
- PAVEMENT REMOVAL, 10"

NOTE:
 BUTT JOINTS WILL BE AT SIDE STREETS, AT LIMITS OF THE PROJECT AND AT OTHER LOCATIONS AS SHOWN ON THE PLANS. ALL BUTT JOINTS ARE INCIDENTAL TO THE SURFACE COURSE.

50 0 50 100
 SCALE IN FEET

FILE NAME =	USER NAME = MAGOLDEN	DESIGNED - LMF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EXISTING CONDITIONS AND REMOVAL PLAN HUNTINGTON DR			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N:\VALGONQUIN\070273\070273\00019\Civil\REM\070273 LAPP Huntington 01.dgn		DRAWN - MDH	REVISED -		SCALE: 50'			08-00075-00-RS	MCHENRY	35	17	
PLOT SCALE = 50'		CHECKED - LMF	REVISED -		SHEET NO. 6 OF 9 SHEETS			CONTRACT NO. 63138				
PLOT DATE = 2/13/2009		DATE - 2/13/2009	REVISED -		STA. 250+00 TO STA. 283+00			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				