



- LEGEND**
- HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH (3.2 INCHES TO 4.1 INCHES)
 - HOT-MIX ASPHALT SURFACE REMOVAL, 3"
 - HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"
 - HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"
 - SIDEWALK REMOVAL
 - BUTT JOINT
 - DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT
 - PAVEMENT REMOVAL, 10"
- NOTE:**
 BUTT JOINTS WILL BE AT SIDE STREETS, AT LIMITS OF THE PROJECT AND AT OTHER LOCATIONS AS SHOWN ON THE PLANS. ALL BUTT JOINTS ARE INCIDENTAL TO THE SURFACE COURSE.

FILE NAME = N:\ALGONGUIN\070273\0702\3\00019\C:\I\REM070273 LAPP Sandbloom-2.dgn	USER NAME = MAGOLDEN	DESIGNED - LMF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EXISTING CONDITIONS AND REMOVAL PLAN SANDBLOOM RD - 2				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50'	DRAWN - MDH	REVISED -		SCALE: 50'	SHEET NO. 8 OF 9 SHEETS	STA. 428+00 TO STA. 454+00	08-00075-00-RS	MCHENRY	35	19		
	PLOT DATE = 2/13/2009	CHECKED - LMF	REVISED -						CONTRACT NO. 63138				
		DATE - 2/13/2009	REVISED -						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				