

SCHEDULE OF QUANTITIES

63500105 DELINEATORS

EACH	LOCATION
IL 251	
1	Sta 448 + 61 LT
1	Sta 448 + 61 RT
1	Sta 641 + 70 RT
1	Sta 642 + 40 LT
4	TOTAL

66500105 WOVEN WIRE FENCE, 4'

FOOT	LOCATION
IL 251	
125	Sta 448 + 10 - 449 + 20
125	TOTAL

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION
IL 251	
1	Sta 447 + 75 60' RT
1	Sta 448 + 25 110' RT
1	Sta 449 + 00 110' RT
1	Sta 449 + 25 60' RT
1	Sta 641 + 00 60' LT
1	Sta 641 + 50 70' LT
1	Sta 642 + 50 70' LT
1	Sta 643 + 00 60' LT
1	Sta 641 + 00 60' RT
1	Sta 641 + 50 80' RT
1	Sta 643 + 00 80' RT
1	Sta 643 + 50 60' RT
12	TOTAL

66700305 PERMANENT SURVEY MARKER, TYPE II

EACH	LOCATION
IL 251	
1	Sta 447 + 00 - 450 + 50 (As Directed by the Engineer)
1	Sta 640 + 00 - 644 + 10 (As Directed by the Engineer)
2	TOTAL

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
IL 251	
900	Sta 446 + 50 - 451 + 00 LT - White EOP (2 applications)
225	Sta 446 + 50 - 451 + 00 CL - Yellow Skip Dash (2 applications)
900	Sta 446 + 50 - 451 + 00 RT - White EOP (2 applications)
820	Sta 640 + 00 - 644 + 10 LT - White EOP (2 applications)
205	Sta 640 + 00 - 644 + 10 CL - Yellow Skip Dash (2 applications)
820	Sta 640 + 00 - 644 + 10 RT - White EOP (2 applications)
3870	TOTAL

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION
IL 251	
6	Sta 446 + 50 - 451 + 00 CL (80' CENTERS)
6	Sta 640 + 00 - 644 + 10 CL (80' CENTERS)
12	TOTAL

78300200 RAISED REFLECTIVE MARKER REMOVAL

EACH	LOCATION
IL 251	
6	Sta 446 + 50 - 451 + 00 CL (80' CENTERS)
6	Sta 640 + 00 - 644 + 10 CL (80' CENTERS)
12	TOTAL

Z0005400 BREAKER-RUN CRUSHED STONE

TON	LOCATION
IL 251	
120	Sta 448 + 61 (111' x 16.25' x 1.0') / 27 x 1.8
131	Sta 642 + 05 (40.7' x 32.25' x 1.5') / 27 x 1.8 EAST END
131	Sta 642 + 05 (40.7' x 32.25' x 1.5') / 27 x 1.8 WEST END
383	TOTAL

A2006714 TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED

EACH	LOCATION
IL 251	
39	Sta 447 + 00 - 450 + 50 To Be Located by Landscape Architect
39	TOTAL

XX005381 SLOPED HEADWALL, TYPE 1

EACH	LOCATION
IL 251	
1	Sta 642 + 00 @ 61.5' LT
1	Sta 642 + 24 @ 59.5' LT
1	Sta 642 + 29 @ 58.9' LT
1	Sta 642 + 40 @ 57.7' LT
4	TOTAL

X0323660 DROP BOX, NO. 1

EACH	LOCATION
IL 251	
1	Sta 448 + 61 Lt
1	TOTAL