

GENERAL NOTES, CONTINUED

THE FOLLOWING ROUTES ARE CONSIDERED GOOD NEIGHBOR ROUTES AND THE DISTRICT GOOD NEIGHBOR POLICY WILL APPLY TO THEM:

FREEPORT ROAD FROM IL 64 TO LANARK
 LANARK ROAD FROM OGLE/CARROLL COUNTY LINE TO FREEPORT ROAD
 GOOSE HOLLOW ROAD FROM US 52 TO FREEPORT ROAD

THE PAY ITEMS AND QUANTITIES LISTED BELOW (ESTIMATED ON A 5% BASE OF THE TOTAL QUANTITIES) ARE GOING TO BE USED IF NEEDED ON THE ABOVE GOOD NEIGHBOR ROUTES:

HOT- MIX ASPHALT SURFACE COURSE, SPECIAL, 470 TON
 AGGREGATE SHOULDERS, TYPE B, 153 TON
 AGGREGATE SURFACE COURSE, TYPE A, 9 TON
 SHORT-TERM PAVEMENT MARKING, 211 FOOT
 WORK ZONE PAVEMENT MARKING REMOVAL, 71 SQ FT
 PAINT PAVEMENT MARKING - LINE 4", 4870 FOOT
 TRAFFIC CONTROL AND PROTECTION STANDARD 701201, 1 L SUM

TREE REPLACEMENT:

- 1) LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT.
- 2) MULCH SHALL BE HARDWOOD WOOD CHIPS, 5 FOOT WIDTH, 4 INCHES THICK WITH WEED BARRIER FABRIC.
- 3) PREDATOR PROTECTION: WITHIN SEVEN (7) DAYS AFTER PLANTING THE TREE TRUNKS SHALL BE WRAPPED FROM THE GROUND LINE TO A HEIGHT OF THREE (3) FEET WITH A ONE-HALF (1/2) INCH SQUARE MESH, GALVANIZED, STEEL WIRE WITH A MINIMUM GAUGE OF 19 (HARDWARE CLOTH) AT A DIAMETER OF 14 INCHES MEASURED FROM THE CENTER OF THE TRUNK WITH A FOUR (4) INCH OVERLAP. THE SCREEN WIRE SHALL BE SECURED WITH A MINIMUM OF FOUR (4) STEEL STAPLES (HOC RINGS).

SURVEY MARKERS:

ONE SURVEY MARKER IS TO BE INSTALLED ON THE EAST END OF THE PROPOSED BRIDGE. AN EXISTING SURVEY MARKER IS LOCATED NEAR THE FIELD ENTRANCES AT THE WEST END OF THE PROJECT. THE CONTRACTOR SHALL ATTEMPT TO AVOID DISTURBING THE EXISTING SURVEY MARKER. A QUANTITY FOR REPLACING THE EXISTING SURVEY MARKER HAS BEEN INCLUDED IN CASE THE EXISTING SURVEY MARKER IS DISTURBED.

FILE NAME = \$FILEL\$	USER NAME = \$USER\$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, IDOT HIGHWAY STANDARDS, GENERAL NOTES & COMMITMENTS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = \$SCALE\$	DRAWN -	REVISED -			17	101BR-4	OGLE	60	3
	PLOT DATE = \$DATE\$	CHECKED -	REVISED -			CONTRACT NO. 64011				
		DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
				SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.						