

PAY CODE #	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				80% FEDERAL 20% STATE ROADWAY X081-2A	100% STATE NON PARTICIPATING X081-2A	80% FEDERAL 20% STATE BRIDGE X081-2A	80% FED. 20% ST. GOOD NEIGHBOR POLICY X081-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	170	170			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	252	252			
20200100	EARTH EXCAVATION	CU YD	1540	1540			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	750			750	
20300100	CHANNEL EXCAVATION	CU YD	3474	3474			
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	240			240	
20800150	TRENCH BACKFILL	CU YD	39	39			
* 25000210	SEEDING, CLASS 2A	ACRE	1	1.00			
* 25000310	SEEDING, CLASS 4	ACRE	0.5	0.50			
* 25000750	MOWING	ACRE	1.00		1.00		
* 25100115	MULCH, METHOD 2	ACRE	1.00	1.00			
* 25100630	EROSION CONTROL BLANKET	SQ YD	906	906			
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	489	489			
* 25100900	TURF REINFORCEMENT MAT	SQ YD	901	901			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	676	676			
28000300	TEMPORARY DITCH CHECKS	EACH	50	50			
28000400	PERIMETER EROSION BARRIER	FOOT	317	317			
28000500	INLET AND PIPE PROTECTION	EACH	1	1			
28000510	INLET FILTERS	EACH	2	2			
28100105	STONE RIPRAP, CLASS A3	SQ YD	83	83			
28100107	STONE RIPRAP, CLASS A4	SQ YD	1490			1490	
28200200	FILTER FABRIC	SQ YD	1573	83		1490	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	213	213			
35101400	AGGREGATE BASE COURSE, TYPE B	TON	50	50			
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	9				9
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	120	120			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	201	201			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	202	202			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	217	217			
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	71	71			
44000100	PAVEMENT REMOVAL	SQ YD	397	397			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	968	968			
44000700	APPROACH SLAB REMOVAL	SQ YD	165	165			
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	1512	1512			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	153				153
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	938	938			
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1	

* SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SEETS	SEET NO.
#FILE#		DRAWN -	REVISED -		SCALE: NTS	SEET NO. OF SEETS	STA.	TO STA.	17	101BR-4	OGLE	60	4
		CHECKED -	REVISED -						CONTRACT NO. 64D11				
		DATE -	REVISED -						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				