

PAY CODE #	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			80% FED. 20% ST. GOOD NEIGHBOR POLICY X081-2A
				80% FEDERAL 20% STATE ROADWAY X081-2A	100% STATE NON PARTICIPATING X081-2A	80% FEDERAL 20% STATE BRIDGE X081-2A	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1			
50200100	STRUCTURE EXCAVATION	CU YD	260			260	
50300225	CONCRETE STRUCTURES	CU YD	44.3			44.3	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	167.9			167.9	
50300260	BRIDGE DECK GROOVING	SQ YD	344			344	
50300280	CONCRETE ENCASEMENT	CU YD	6.6			6.6	
50300300	PROTECTIVE COAT	SQ YD	464			464	
50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	608			608	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	33893			33893	
50800515	BAR SPLICERS	EACH	62			62	
51201800	FURNISHING STEEL PILES HP14X73	FOOT	259			259	
51500100	NAME PLATES	EACH	1			1	
54200673	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 48"	FOOT	46	46			
54213447	END SECTIONS 12"	EACH	2	2			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	14	14			
550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	22	22			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	120			120	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	115			115	
60240324	INLETS, TYPE B, TYPE 20 FRAME AND GRATE	EACH	2	2			
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	550	550			
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4			
63200310	GUARDRAIL REMOVAL	FOOT	743	743			
63500105	DELINEATORS	EACH	4	4			
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8	8			
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1				1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	211				211
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	71				71
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	9745	4875			4870
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16			
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	4	4			
* 78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	4	4			
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	24	24			
X0324856	SLOPED METAL END SECTION WITH GRATE, 48 INCH	EACH	2	2			

* SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SEETS	SEET NO.
#FILEL#		DRAWN -	REVISED -						17	101BR-4	OGLE	60	5
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		SCALE: NTS	SEET NO. OF SEETS	STA. TO STA.	CONTRACT NO. 64011					
	PLOT DATE = #DATE#	DATE -	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					